

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-051-23587-00-00  
Spot: W2NESESE Sec/Twnshp/Rge: 3-12S-18W  
990 feet from S Section Line, 510 feet from E Section Line  
Lease Name: LEIKAM Well #: 1  
County: ELLIS Total Vertical Depth: 3770 feet

Operator License No.: 6931  
Op Name: BOWMAN OIL COMPANY, A GENERAL  
Address: 805 CODELL RD  
CODELL, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3769		200 SX
SURF	8.625	220		100 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/11/2017 9:30 AM  
Plug Co. License No.: 6931 Plug Co. Name: BOWMAN OIL COMPANY, A GENERAL PARTNERSHIP  
Proposal Rcvd. from: BILL BOWMAN Company: BOWMAN OIL COMPANY, A GENE Phone: (785) 259-1297

Proposed Plugging Method: Ordered 325 sx 60/40 pozmix 4% gel cement w/600 # hulls.  
DV Tool at 1374'.  
Casing leaks at 2100' - 2500' squeezed.  
Perforations: 3640' - 3648', 3654' - 3657' and 3662' - 3667'

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/11/2017 3:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Bowman ran in hole with tubing to 3620'. Swift rigged to tubing and pumped 120 sx cement w/300 # hulls mixed in. Pulled tubing to 1779'. Pumped 120 sx cement w/300 # hulls mixed in to circulate cement up 4 1/2' casing. Pulled tubing. Topped 4 1/2" casing with 50 sx cement. Well was drinking fluids. Left set 2 hours. Rigged to 8 5/8" with instant pressure. 3:00pm - Topped off with 10 sx cement. Hole standing full.

GPS: 39.03341 -099.29897

Perfs:

Top	Bot	Thru	Comments
3662	3667		
3654	3657		
3640	3648		

Remarks: SWIFT CEMENTING CO TICKET # 30522

Plugged through: TBG

INVOICED  
REV - 2 2017

District: 04

Signed

KCC WICHITA

  
(TECHNICIAN)

CM

OCT 30 2017

RECEIVED

OCT 13 2017