

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-207-01409-00-00
Spot: NENENE Sec/Twnshp/Rgc: 29-23S-14E
4950 feet from S Section Line, 330 feet from E Section Line
Lease Name: MACLASKEY Well #: 3
County: WOODSON Total Vertical Depth: 1688 feet

Operator License No.: 34827

Op Name: C3OIL, LLC

Address: 600 ARROWHEAD DR
NEW STRAWN, KS 66839

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	6.625	1664		145 SX
SURF	12.5	40		20 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 10/16/2017 10:00 AM

Plug Co. License No.: 33413

Plug Co. Name: TITUS WELL SERVICE LLC

Proposal Revd. from: CHRIS HAAS

Company:

Phone: (913) 515-5329

Proposed Plugging Method: 3" Completion cemented to the top when the liner was ran in the early 1980s. Rig up, run 2 1/16 tubing to TD. Set cement plug at 1688' with 10 SKS. Pull tubing to 1100' (Douglas formation) set cement plug with 10 SKS. Pull tubing to 250' set cement plug with 25 SKS. Fill well to top with cement.

Plugging Proposal Received By: MICHAEL HEFFERN

Witness Type: NONE

Date/Time Plugging Completed: 10/16/2017 2:00 PM

KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

Perfs:

Ran tubing to 1615', pumped 10 sxs cement, pulled tubing to 1045", pumped 10 sxs cement, pulled tubing to 262' pumped 45 sxs cement to surface, gel spacers between cement plugs.

RECEIVED
KCC DIST # 3
OCT 24 2017
CHANUTE, KS

mt

INVOICED
NOV - 6 2017

Remarks:

Plugged through: TBG

District: 03

Signed Mike Heffern
(TECHNICIAN)

810 E 7th
 PO Box 92
 EUREKA, KS 67045
 (620) 583-5561



Cement or Acid Field Report
 Ticket No. **3574**
 Foreman Steve Mead
 Camp Eureka KS

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State	
10-16-17	1021	Maclasky #3				Woodson	KS	
Customer C 3 Oil			Safety Meeting		Unit #	Driver	Unit #	Driver
Mailing Address 600 Arrowhead Dr.					104	Alan M.		
City New Strawn					113	Tasen H		
State KS					145	Allen B		
Zip Code 66839								

Job Type PTA old well Hole Depth 1634' Slurry Vol. _____ Tubing _____
 Casing Depth _____ Hole Size _____ Slurry Wt. _____ Drill Pipe _____
 Casing Size & Wt. 3 1/2 Cement Left in Casing _____ Water Gal/SK _____ Other _____
 Displacement _____ Displacement PSI _____ Bump Plug to _____ BPM _____

Remarks: Safety Meeting - Plug well as follow Mix 100% Gel Flash

Spot 10 sks AT 1615'

Spot 10 sks AT 1070'

45 sks 262' to surface

Total 65 sks 60/40 Perm mix Cement 4% Gel

Job Complete

Thank you

INVOICED

NOV - 6 2017

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C105	1	Pump Charge	750.00	750.00
C107	30	Mileage	3.95	118.50
C203	65 sks	60/40 Perm mix Cement	12.75	828.75
C206	200 ^g	Gel 4%	.20	40.00
C206	100 ^g	Gel Flash	.20	20.00
C108A	2.80 ton	Tan Mileage Bulk Trucks	M/C	345.00
C113	3 hr	80001 Vac Trucks	85.00	255.00
<div style="border: 1px solid black; border-radius: 50%; padding: 10px; display: inline-block;"> 590 < 126.11 \$ 2401.33 </div>				
			Sub Total	2357.25
			Sales Tax	176.79
Authorization <u>Witness by Chris Haas</u> Title <u>owner</u>			Total	2534.04

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.