

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-073-30064-00-00
Spot: W2E2NENE Sec/Twnshp/Rge: 24-25S-8E
660 feet from N Section Line, 350 feet from E Section Line
Lease Name: WELSH B Well #: 1
County: GREENWOOD Total Vertical Depth: 2538 feet

Operator License No.: 32701
Op Name: C & G DRILLING, INC.
Address: 701 E. RIVER ST.
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2538		100 SX
SURF	8.625	203		130 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/19/2017 10:00 AM
Plug Co. License No.: 32701 Plug Co. Name: C & G DRILLING, INC.
Proposal Rcvd. from: TIM GULICK Company: _____ Phone: (620) 583-4306

Proposed per state requirements
Plugging
Method:

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: PARTIAL
Date/Time Plugging Completed: 10/23/2017 9:00 AM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

rock bridge @ 2500' 10 sxs cement w/dump baler, cut casing off @ 945' pull casing out, ran tubing to 945', pumped 20 sxs cement, pulled tubing to 250', pumped 10 sxs cement to surface, gel spacers between cement plugs.

Perfs:

RECEIVED
KCC DIST # 3
OCT 31 2017
CHANUTE, KS

MH

Remarks:

Plugged through: TBG

INVOICED
NOV - 6 2017

District: 03

Signed Mik Heffern
(TECHNICIAN)

810 E 7TH
PO Box 92
EUREKA, KS 67045
(620) 583-5561



Cement or Acid Field Report
Ticket No. **3548**
Foreman Rick Ledford
Camp Eureka, KS

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
10-23-17	1037	Welsh B-1				GLW	KS
Customer <u>L+G Drilling</u>			Safety Meeting	Unit #	Driver	Unit #	Driver
Mailing Address <u>701 E. River</u>				102	Rick L.		
City <u>Eureka</u>				110	Jason H		
State <u>KS</u>				120	Allen G.		
Zip Code <u>67045</u>							

Job Type P.T.A Hole Depth _____ Slurry Vol. _____ Tubing 2 3/8"
Casing Depth _____ Hole Size _____ Slurry Wt. _____ Drill Pipe _____
Casing Size & Wt. 4 1/2" Cement Left in Casing _____ Water Gal/SK _____ Other _____
Displacement _____ Displacement PSI _____ Bump Plug to _____ BPM _____

Remarks: Safety meeting. Rig up to 4 1/2" casing. Pump 300" gel spacer ahead mixed 20 srs 100/40 Pozmix cement w/ 4% gel @ 945' Pull 4 1/2" casing out. Run 250' of 2 3/8" tubing back in. Mixed 110 srs cement from 250' to surface, pull tubing out, capped well off. Job complete. Rig down.

"Thank You"

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C-105-2	1	Pump Charge	525.00	525.00
C107	1	Mileage	3.95	n/c
C203	130 srs	100/40 Pozmix cement	12.75	1657.50
C206	450"	4% gel	.20	90.00
C206	300"	gel spacer	.20	60.00
C1074	5.6	ten mileage bulk tax	-.12 / ml	175.00
<div style="border: 1px solid black; border-radius: 50%; padding: 10px; display: inline-block;"> 590 <13418> \$2560.18 </div>				
		Subtotal		2507.50
		Sales Tax		189.06
		Total		2696.56

Authorization by Willy Title Co Rep

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.