

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-207-26771-00-00
Spot: N2NWSW Sec/Twnshp/Rgc: 34-25S-17E
2310 feet from S Section Line, 4620 feet from E Section Line
Lease Name: WHITE Well #: 11
County: WOODSON Total Vertical Depth: 1125 feet

Operator License No.: 34769
Op Name: CHEROKEENRG LLC
Address: 112 SOUTH 5TH STREET P.O. BOX 111
NEODESHA, KS 66757

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	900		180 SX
SURF	8.625	20		4 SX

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 09/12/2017 12:00 AM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Rcvd. from: PAM SCHULTZ Company: _____ Phone: (620) 432-1840

Proposed Plugging Method: Run tubing to bottom, spot 50' plug (5 sacks), pull up to 500', spot 50' plug (5 sacks), pull up to 225', cement to surface, cut wellhead off below plow depth and restore location.

Plugging Proposal Received By: _____ WitnessType: NONE
Date/Time Plugging Completed: 09/12/2017 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Ran 1" pipe down the inside of the 4.5" casing to TD. Mixed and pumped 2 sacks of gel. Pumped and placed 10 sacks of portland cement at TD. Pulled 1" pipe up to 500'. Pumped and placed 7 sack cement plug at 500'. Pulled 1" pipe up to 250'. Pumped and circulated cement from 250' to surface. Pulled the 1" pipe out of casing and topped the well off with cement. A total of 45 sacks of portland cement was reported used to plug this well.

Perfs:

RECEIVED
KCC DIST # 3
OCT 13 2017
CHANUTE, KS

RD

Remarks:

Plugged through: TBG

INVOICED
NOV - 6 2017

District: 03

Signed _____

(TECHNICIAN)