

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-03196-00-01
Spot: NWNESE Sec/Twnshp/Rge: 33-16S-11W
2310 feet from S Section Line, 990 feet from E Section Line
Lease Name: REIMANN Well #: 2
County: BARTON Total Vertical Depth: 3367 feet

Operator License No.: 35280
Op Name: C & K OPERATING LLC
Address: 413 S. MAIN
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3367		100 SX
SURF	8.625	317		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/02/2017 8:00 AM
Plug Co. License No.: 34044 Plug Co. Name: JD'S WELL SERVICE INC.
Proposal Rcvd. from: JIM KRAFT Company: C & K OPERATING LLC Phone: (620) 672-9700

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement, 500 # hulls and 13 sx gel.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/02/2017 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1450', 790' and 300'. Ran tubing to 3200' and pumped 13 sx gel followed by 50 sx cement w/200 # hulls. Pulled tubing to 1450' and pumped 65 sx cement w/200 # hulls. Pulled tubing to 700' and pumped 160 sx cement. Circulated cement to surface on casing. Pulled tubing. Tied to casing and pumped 40 sx cement pressured to 300 psi. Tied to surface pipe and pressured to 300 psi. Would not take any cement.

GPS: 38.61529 -098.53873

Perfs:

Remarks: COPELAND ACID AND CEMENTING

Plugged through: TBG

District: 04

Signed

Bruce Rodie

(TECHNICIAN)

CM

OCT 8 5 2017

INVOICED
OCT - 6 2017

KCC WICHITA
OCT 17 2017
RECEIVED