

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-19374-00-00
Spot: NESWNE Sec/Twnshp/Rge: 19-29S-8E
4301 feet from S Section Line, 2338 feet from E Section Line
Lease Name: SHINN Well #: 2
County: BUTLER Total Vertical Depth: 2836 feet

Operator License No.: 33192
Op Name: CROWN ENERGY COMPANY
Address: 1117 N.W. 24TH ST.
OKLAHOMA CITY, OK 73106

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2772	45	45 SX
SURF	8.625	27		85 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/10/2017 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICK HART/HAYS WILSON Company: _____ Phone: (405) 526-0111

Proposed Plugging Method: AS PER KCC RULES & REGS. CIBP @ 2750' W/5 SKS. PERF & CIRCULATE 250'-0'.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 10/12/2017 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

PERFORATED SQUEEZE HOLES 250'-251'. (4 HOLES). RIH W/TUBING @ 2700', QWS ESTABLISHED CIRCULATION, MIXED & PUMPED 50 SXS 60/40 POZMIX 4% GEL 3% CC W/100# HULLS. LAYED TUBING DOWN. RIH W/TUBING @ 260', QWS ESTABLISHED CIRCULATION, MIXED & PUMPED 125 SXS 60/40 POZMIX 4% GEL 150# HULLS TO SURFACE. 10-12-2017 RIH WITH 1" INSIDE 8 5/8" SURFACE @ 105'. QWS CIRCUALTED & PUMPED 50 SXS 60/40 POZMIX TO SURFACE. CEMENT CIRCUALTED. LAYED DOWN 1" TUBING. RIH W 1" TUBING INSIDE 5 1/2" CASING @ 85', QWS MIXED & PUMPED 25 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED,

Perfs:

Top	Bot	Thru	Comments
2772	2836	OH	

INVOICE REC'D
NOV - 6 2017

Remarks: COMPLIANCE - DENIED TA

Plugged through: TBG

District: 02

Signed: DUANE KRUEGER
(TECHNICIAN)

JK