

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-015-19373-00-00  
Spot: NWNWSENE Sec/Twnshp/Rge: 19-29S-8E  
3665 feet from S Section Line, 2971 feet from E Section Line  
Lease Name: SHINN Well #: 8  
County: BUTLER Total Vertical Depth: 2815 feet

Operator License No.: 33192  
Op Name: CROWN ENERGY COMPANY  
Address: 1117 N.W. 24TH ST.  
OKLAHOMA CITY, OK 73106

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2768		45 SX
SURF	10	18		0 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/09/2017 8:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICK HART/HAYS WILSON Company: \_\_\_\_\_ Phone: (405) 528-0111

Proposed Plugging Method: AS PER KCC RULES & REGS. CIBP @ 2750' W/5 SKS. PERF & CIRCULATE 250'-0'.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL  
Date/Time Plugging Completed: 10/11/2017 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SET CIBP @ 2750', DUMP BAILED 2 SX CEMENT ON TOP OF PLUG. PERFORATED SQUEEZE HOLES 250'-251'. (4 HOLES). RIH W/TUBING @ 260', QWS MIXED & PUMPED 100 SXS 60/40 POZMIX 4% GEL 2% CC TO SURFACE. WAITED 2 HOURS, DID NOT TAG CEMENT. RIH W/TUBING @ 240', QWS MIXED & PUMPED 125 SXS 60/40 POZMIX 4% GEL 3% CC TO SURFACE. CEMENT CIRCUALTED. 10-11-17 RIH W/TUBING @ 270', QWS ESTABLISHED CIRCULATION, MIXED & PUMPED 50 SXS 60/40 POZMIX 3% CC W/100# HULLS. WAITED 2 HOURS, TAGGED CEMENT PLUG @ 115', RIH W/TUBING @ 115', QWS ESTABLISHED CIRCULATION, MIXED & PUMPED 25 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCUALTED. PLUG DOWN 5:00 PM 10-11-2017.

Perfs:

Top	Bot	Thru	Comments
2768	2815	OH	

INVOICED  
10/11 - 8 2017

Remarks: COMPLIANCE - DENIED TA

Plugged through: TBG

District: 02

Signed DUANE KRUEGER  
(TECHNICIAN)

JK