

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-19375-00-00
Spot: NENWSENE Sec/Twnshp/Rge: 19-29S-8E
3653 feet from S Section Line, 2333 feet from E Section Line
Lease Name: SHINN Well #: 12
County: BUTLER Total Vertical Depth: 2850 feet

Operator License No.: 33192
Op Name: CROWN ENERGY COMPANY
Address: 1117 N.W. 24TH ST.
OKLAHOMA CITY, OK 73106

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2850		25 SX
SURF	10.75	40		24 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/16/2017 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICK HART/HAYS WILSON Company: _____ Phone: (405) 526-0111

Proposed Plugging Method: AS PER KCC RULES & REGS. CIBP @ 2750' W/4 SXS. PERF & CIRCULATE. 250'-0'.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 10/19/2017 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

Perfs:

RIH ON WIRELINE, SET CIBP @ 2770', DUMP BAILED 2 SXS CEMENT ON TOP OF PLUG. PERFERATED SQUEEZE HOLES 250'-251' (4 HOLES). RIH W/TUBING @ 260', QWS MIXED & PUMPED 100 SXS 60/40 POZMIX 4% GEL 2% CC & 100# HULLS. LAYED DOWN TUBING, SWEDGED INTO CASING. QWS MIXED & PUMPED 75 SXS 60/49 POZMIX 4% GEL 2% CC TO SURFACE. CEMENT CIRCULATED. 10-19-2017 TOPPED WELL BACK TO SURFACE W/25 SXS.

INVOICED
NOV - 8 2017

Remarks: COMPLIANCE - DENIED TA

Plugged through: TBG

District: 02

Signed DUANE KRUEGER
(TECHNICIAN)

1/2