

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-009-26180-00-00  
Spot: SESWSWNW Sec/Twnshp/Rge: 32-20S-13W  
2697 feet from S Section Line, 585 feet from W Section Line  
Lease Name: GAUNT-WRIGHT UNIT Well #: 1-32  
County: BARTON Total Vertical Depth: 3579 feet

Operator License No.: 5088

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	370		250 sx

Op Name: DARRAH, JOHN JAY, JR.

Address: P.O. BOX 2786  
WICHITA, KS 67201

Well Type: DH

UIC Docket No:

Date/Time to Plug: 09/21/2017 12:00 AM

Plug Co. License No.: 33905

Plug Co. Name: ROYAL DRILLING INC

Proposal Rcvd. from: DOUG

Company: ROYAL DRILLING INC

Phone: (785) 735-4142

Proposed Plugging Method: Ordered 235 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: DARREL DIPMAN

Witness Type: NONE

Date/Time Plugging Completed: 09/21/2017 6:00 AM

KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Perfs:

1st plug @3540 w/50 sx  
2nd plug @800 w/50 sx  
3rd plug @385 w/100 sx  
4th plug @40 w/10 sx

Rathole 30 sx Mousehole 15 sx

Remarks: GLOBAL

Plugged through: DP

INVOICED  
NOV - 7 2017  
NOV - 6 2017

District: 04

Signed

Darrel Dipman  
(TECHNICIAN)

CM

OCT 05 2017

KCC WICHITA

Form CP-2/3

OCT 17 2017

RECEIVED