

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-30004-00-00
Spot: NESWSE Sec/Twnshp/Rge: 30-31S-6E
1102 feet from S Section Line, 1658 feet from E Section Line
Lease Name: BURDEN UNIT Well #: 5
County: COWLEY Total Vertical Depth: 2988 feet

Operator License No.: 30169
Op Name: DOUBLE "D" OIL COMPANY, INC.
Address: 2009 JEAN CT
WINFIELD, KS 67156

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|------|------------|-------------|----------|
| PROD | 4.5 | 2985 | | 50 SX |
| SURF | 7 | 202 | | 135 SX |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/09/2017 8:00 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: DON BUTLER Company: DOUBLE D OIL COMPANY Phone: (620) 221-3570

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL
Date/Time Plugging Completed: 10/10/2017 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TUBING @ 2986', BUTLER BROTHERS MIXED & PUMPED 15 SXS CLASS A COMMON & DISPLACED IN CASING. TAGGED CEMENT @ 2860'. CUT CASING @ 502', LAYED DOWN 4 1/2" CASING. RIH W/TUBING @ 350', BUTLER BROTHERS CIRCULATED 120 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. CEMENT TICKET / DANIELS READY MIX #038605.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 2985 | 2988 | OH | |

INVOICED
10/10/2017

Remarks: COMPLIANCE - DENIED TA

Plugged through: TBG

District: 02

Signed DUANE KRUEGER
(TECHNICIAN)

DK