

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-035-19349-00-00  
Spot: SWNESW Sec/Twnshp/Rge: 30-31S-6E  
1664 feet from S Section Line, 3638 feet from E Section Line  
Lease Name: BURDEN UNIT Well #: 15-2  
County: COWLEY Total Vertical Depth: 2999 feet

Operator License No.: 30169  
Op Name: DOUBLE "D" OIL COMPANY, INC.  
Address: 2009 JEAN CT  
WINFIELD, KS 67156

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2999		90 SX
SURF	8.625	217		85 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/19/2017 8:00 AM  
Plug Co. License No.: 5495 Plug Co. Name: MCPHERSON, BILL AND/OR PENNY M. DBA MCPHERSON DRILLING  
Proposal Rcvd. from: DON BUTLER Company: \_\_\_\_\_ Phone: (620) 221-3570

Proposed Plugging Method: AS PER KCC RULES & REGS. CEMENT BACK TO 2880'. PERF & CIRCULATE 250'-0'.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL  
Date/Time Plugging Completed: 10/19/2017 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report: \_\_\_\_\_ Perfs: \_\_\_\_\_

RIH W/TUBING @ 2994, BUTLER BROTHERS MIXED & PUMPED 15 SXS CLASS A COMMON & DISPLACED IN CASING. TAGGED CEMENT @ 2829'. CUT CASING @ 345', LAYED DOWN 345' 4 1/2" CASING. RIH W/TUBING @ 350', BUTHER BROTHERS ESTABLISHED CIRCULATION, MIXED & PUMPED 120 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCUALTED. DANIELS READY MIX CEMENT TICKET #038653.

INVOICED  
NOV - 7 2017

Remarks: COMPLIANCE - DENIED TA

Plugged through: TBG

District: 02

Signed DUANE KRUEGER  
(TECHNICIAN)

18