

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-15968-00-00
Spot: NESESW Sec/Twnshp/Rge: 32-16S-13W
990 feet from S Section Line, 2970 feet from E Section Line
Lease Name: RUDE Well #: 2
County: BARTON Total Vertical Depth: 3332 feet

Operator License No.: 34506
Op Name: EMPIRE ENERGY E&P, LLC
Address: 345 RIVERVIEW ST., STE 540
WICHITA, KS 67203

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	6	3323		100 SX
SURF	10.75	368		350 SX

Well Type: CIL UIC Docket No: _____ Date/Time to Plug: 08/28/2017 8:30 AM
Plug Co. License No.: 35478 Plug Co. Name: LEIKER WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD LACEY Company: EMPIRE ENERGY E&P, LLC Phone: (620) 617-0603

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement
Tubing fish at 583'.
Got rods and pump out of hole.
Squeeze @444'-496' w/250 sx
KC perfs only.
Tried spear and overshot for 2 days then went outside casing.
Tubing swiss cheese. Losing fluid.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/28/2017 11:30 AM KCC Agent: RAY DINKEL

Actual Plugging Report:

Hooked to 6" casing and pumped 120 sx cement. Pressured to 600 psi. Pressure dropped to 250 psi. Kicked pump in pressure right up to 600 psi. Shut in. Hooked to braden head and pumped 10 sx cement. Pressured to 200 psi.

GPS: 38.61151 -098.78606

Perfs:

Top	Bot	Thru	Comments
3285	3290		
3266	3270		
3244	3248		
3184	3200		
3130	3140		
3108	3116		

INVOICED
NOV - 7 2017

Remarks: COPELAND ACID AND CEMENTING TICKET # 45584

Plugged through: CSG

KCC WICHITA

OCT 17 2017

District: 04

Signed

Ray Dinkel

(TECHNICIAN)

RECEIVED

CM