

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-073-24030-00-00  
Spot: NWNESESE Sec/Twnshp/Rge: 20-26S-10E  
1040 feet from S Section Line, 540 feet from E Section Line  
Lease Name: HUNTINGTON Well #: 16-20  
County: GREENWOOD Total Vertical Depth: 2696 feet

Operator License No.: 35018  
Op Name: ENTRANSCO ENERGY, LLC  
Address: PO BOX 578  
DEWEY, OK 74029

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2692		300 SX
SURF	8.625	52		40 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/25/2017 10:30 AM  
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC  
Proposal Rcvd. from: RAY GILBERT Company: \_\_\_\_\_ Phone: (620) 820-9687

Proposed Plugging Method: Plug well per KCC regulations

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/25/2017 2:30 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

Ran tubing to 2550', pumped 5 sxs cement, pulled tubing to 1000', pumped 5 sxs cement, pulled tubing to 200' pumped 35 sxs cement to surface, gel spacers between cement plugs.

Perfs:

RECEIVED  
KCC DIST # 3  
OCT 31 2017  
CHANUTE, KS

MH

INVOICED  
NOV - 7 2017

Remarks:

Plugged through: TBG

District: 03

Signed Mick Hoff  
(TECHNICIAN)

**STATEMENT**

13161

**ELMORE'S INC.**

Box 87 - 776 HWY 99  
 Sedan, KS 67361  
 Cell: (620) 249-2519  
 Eve: (620) 725-5538

Date  
 10-25-17

Customer Entranco Energy LLC  
 Address \_\_\_\_\_  
 City \_\_\_\_\_ State \_\_\_\_\_ Zip \_\_\_\_\_

Qty.	Description	Price	Amount
12 hr	Pulling Unit	120.00	1440.00
3 hr	Cement Pump	120.00	360.00
3 hr	Water Truck	85.00	255.00
1	Bank Tank	85.00	85.00
2550'	1" Tubin	.10	255.00
4	skc Coel	16.00	64.00
50	skc Cement	12.50	625.00
1	hr Backhoe	85.00	85.00
1	Cut off Cables	100.00	100.00
	Plug Job Huntington 16-20		3269.00
	Pulled Out Raker Tubin	Top .75	245.18
	Ran 1" To 2550' Gel Hole	#	3514.18
	Spotted 10 skc Cement Pulled		
	Up to 1000' Spotted 5 skc Cement		
	Pulled Up to 150' Cemented To		
	Surface With 20 SK Top Plug Fall		
	To 200' Topped off Well With 15SK Cut-off Cables		

Thank You - We appreciate your business! C. J. Seel 'D.H.

Rec'd. by \_\_\_\_\_

TERMS: Account due upon receipt of services. A 1 1/2% Service Charge, which is an annual percentage rate of 18% will be charged to accounts after 30 days.