

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-193-20576-00-00
Spot: S2NENWNW Sec/Twnshp/Rge: 23-10S-31W
4934 feet from S Section Line, 4290 feet from E Section Line
Lease Name: BIXENMAN Well #: 1
County: THOMAS Total Vertical Depth: 4650 feet

Operator License No.: 5316
Op Name: FALCON EXPLORATION, INC.
Address: 125 N MARKET STE 1252
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4648		225 SX
SURF	8.625	350		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/20/2017 10:00 AM
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC
Proposal Rcvd. from: CYNDE WOLF Company: FALCON EXPLORATION, INC. DBA Phone: (316) 262-1378

Proposed Plugging Method: Ordered 420 sx 60/40 pozmix 4% gel cement and 500 # hulls.
8 5/8" surface casing set at 350' w/200 sx cement.
4 1/2" production casing set at 4648' w/225 sx cement.
Stage Collar at 1774' w/215 sx cement.
TD 4650'. PBD 4610'.
Perforations: 4400' - 4404' and 4416' - 4421'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/20/2017 2:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Perforated production casing at 2547'. Ran tubing to 4350' and pumped 95 sx cement w/250 # hulls. Pulled tubing to 2950' and pumped 95 sx cement w/150 # hulls. Pulled tubing to 1500' and pumped 120 sx cement w/100 # hulls. Circulated cement to surface. Pulled tubing to surface. Connected to 4 1/2" production casing and pumped 10 sx cement. Connected to 8 5/8" surface casing and pumped 20 sx cement. Pressured to 300 psi.

GPS: 39.17591N -100.75499W

Perfs:

Top	Bot	Thru	Comments
4416	4421		
4400	4404		

Remarks: FRITZLER SERVICE UNIT AND GLOBAL OILFIELD SERVICES TICKET # 3104

Plugged through: TBG

District: 04

Signed

Darrel Dipman

(TECHNICIAN)

CM

KCC WICHITA

OCT 30 2017

RECEIVED

OCT 23 2017

INVOICED
10/17 - 7 2017