

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-22851-00-00
Spot: NWSWNWNE Sec/Twnshp/Rge: 15-10S-21W
950 feet from N Section Line, 2560 feet from E Section Line
Lease Name: MCVEY/COOK Well #: 1
County: GRAHAM Total Vertical Depth: 3858 feet

Operator License No.: 5135
Op Name: FARMER, JOHN O., INC.
Address: 370 W WICHITA AVE PO BOX 352
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3840		125 SX
SURF	8.625	212		160 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/16/2017 10:00 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: DUANE EICHMAN Company: FARMER, JOHN O., INC. Phone: (785) 483-8355

Proposed Plugging Method: Ordered 375 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Perforations: 3544' - 3555'.
Port Collar at 1698' w/425 sx cement.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/16/2017 1:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3480' and pumped 75 sx cement w/200 # hulls. Pulled tubing to 2480' and pumped 75 sx cement. Pulled tubing to 1480' and pumped 90 sx cement. Cement circulated. Pulled tubing out. Topped off casing with 20 sx cement. Backside full of cement. Shut in pressure 300 psi.

GPS: 39.18822 -099.65157

Perfs:

Top	Bot	Thru	Comments
3544	3555		

INVOICED
NOV - 8 2017


Remarks: QUALITY CEMENT TICKET # 426

Plugged through: TBG

District: 04

KCC WICHITA

Signed



(TECHNICIAN)

CM

OCT 30 2017

RECEIVED

OCT 17 2017