

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-167-21351-00-00  
Spot: NWSESW Sec/Twnshp/Rge: 16-15S-13W  
990 feet from S Section Line, 3630 feet from E Section Line  
Lease Name: RUPPENTHAL Well #: 5  
County: RUSSELL Total Vertical Depth: 3333 feet

Operator License No.: 7383  
Op Name: GRADY BOLDING CORPORATION  
Address: 114 NORTH MAIN P.O. BOX 486  
ELLINWOOD, KS 67526

| String | Size  | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD   | 5.5   | 3326       |             | 100 SX   |
| SURF   | 8.625 | 557        |             | 275 SX   |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/10/2017 7:30 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: LYLE L. GUNN Company: GRADY BOLDING CORPORATION Phone: (620) 564-2240

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/400 # hulls.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/10/2017 10:00 AM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perfs:

09/09/2017 - Sanded off perforations and placed 5 sx cement on top. Operator decided not to pull casing. Perforated at 1450', 855' and 560'. Ran tubing to 1500' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 580' and pumped 50 sx cement. Circulated cement to pit. Closed backside valve and pumped 80 sx cement. Circulated cement to pit. POOH. Pumped 5 sx cement until it circulated the braden head. Shut in.

GPS: 38.74318 -098.77594

Remarks: QUALITY CEMENTING TICKET # 420

Plugged through: TBG

INVOICED  
NOV - 9 2017

District: 04

Signed

Ray A. Dinkel

(TECHNICIAN)

CM

KCC WICHITA

OCT 30 2017

RECEIVED

OCT 13 2017