

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-115-21383-00-00
Spot: SENW Sec/Twnshp/Rge: 8-19S-1E
1980 feet from N Section Line, 1980 feet from W Section Line
Lease Name: G - F, INC. Well #: 1
County: MARION Total Vertical Depth: 2931 feet

Operator License No.: 5120
Op Name: RANGE OIL COMPANY, INC.
Address: 9412 E. CENTRAL PO BOX 781775
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	4.5	2860		
PROD	4.5	2930		185 SX
SURF	8.625	293		160 SX
T1	2.375	2922		

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/30/2017 12:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: ALAN NATION Company: RANGE OIL CO Phone: (620) 222-4304

Proposed Plugging Method: AS PER KCC RULES & REGS. SET CIBP @ 2860' TOP WITH 4 SX COMMON CEMENT TAG PERF @ 343' AND CIRCULATE TO SURFACE.

Plugging Proposal Received By: _____ Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/30/2017 12:00 PM KCC Agent: JERRY SPARLING

Actual Plugging Report:

SET CIBP @ 2860' TOPPED WITH 4 SX COMMON CEMENT TAGGED @ 2825'. PERFORATED AT RAN 1" TO 440' PUMPED 150 SX COMMON CEMENT (LEVEL FELL BACK) PULLEE 1", AND SWAGED TO 4.5 PRODUCTION STRING PUMPED 50 SX AND LEVEL FELL BACK. 10-30-2017. CREW PUMPED 35 SX COMMON CEMENT TO TOP OFF.

Perfs:

Top	Bot	Thru	Comments
2901	2908	CSG	

INVOICED
NOV - 9 2017

Remarks: QUALITY WELL SERVICE, TA EXPIRED 9-22-2017

Plugged through: CSG

District: 02

Signed Jerry Spurling
(TECHNICIAN)

1/2