

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-193-21002-00-00
Spot: NWSWSE Sec/Twnshp/Rge: 30-6S-35W
953 feet from S Section Line, 2299 feet from E Section Line
Lease Name: Z. BAIRD Well #: 1
County: THOMAS Total Vertical Depth: 4814 feet

Operator License No.: 5046
Op Name: RAYMOND OIL COMPANY, INC.
Address: PO BOX 48788
WICHITA, KS 67201

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	302		200 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 10/23/2017 12:00 AM
Plug Co. License No.: 6039 Plug Co. Name: L. D. DRILLING, INC.
Proposal Rcvd. from: RICK Company: L. D. DRILLING, INC. Phone: (620) 617-4794

Proposed Plugging Method: Ordered 240 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: NONE
Date/Time Plugging Completed: 10/23/2017 12:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perfs:

1st plug @2905 w/50 sx
2nd plug @2020 w/100 sx
3rd plug @350 w/50 sx
4th plug @40 w'10 sx

Rathole 30 sx

Remarks: CONSOLIDATED

Plugged through: DP

INVOICED
NOV - 8 2017

District: 04

KCC WICHITA

OCT 30 2017

RECEIVED

Richard Williams

(TECHNICIAN)

CM

OCT 24 2017

Form CP-2/3