

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-22516-00-01
Spot: N2NWNW Sec/Twnshp/Rge: 35-8S-22W
4950 feet from S Section Line, 4620 feet from E Section Line
Lease Name: BUSS OWWO Well #: 1
County: GRAHAM Total Vertical Depth: 3830 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3827		150 SX
SURF	8.625	220		155 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/18/2017 10:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC.
Proposal Rcvd. from: TOMMY ATKINS Company: RITCHIE EXPLORATION, INC. Phone: (785) 216-0155

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls.
8 5/8" surface casing set at 220' w/155 sx cement.
4 1/2" production casing set at 3827' w/150 sx cement.
Casing leaks: 2800' - 3200'.
TD 3830'. PBTD 3730'.
Port Collar set at 1750' w/300 sx cement. Anhydrite 1764'.
Perforations: 3439' - 3444', 3474' - 3475', 3510' - 3512', 3519' - 3522', 3570' - 3574', 3594' - 3597', 3604' - 3608', 3683' - 3688' and 3800' - 3804'.
CIBP set at 3780'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/19/2017 12:15 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Ran tubing to 3400' and pumped 85 sx cement w/300 # hulls. Pulled tubing to 2400' and pumped 80 sx cement w/200 # hulls. Pulled tubing to 1200' and pumped 85 sx cement. Cement circulated to surface. Pulled tubing to surface. Connected to 4 1/2" production casing and pumped 15 sx cement. Connected to 8 5/8" surface casing and pumped 20 sx cement. Pressured to 300 psi.

GPS: 39.32042N -099.75113W

Perfs:

Top	Bot	Thru	Comments
3800	3804		
3683	3688		
3520	3522		
3510	3512		
3474	3475		
3439	3608		

Remarks: GLOBAL OILFIELD SERVICES LLC TICKET # 3118

Plugged through: TBG

District: 04

KCC WICHITA *Darrel Dipman*

(TECHNICIAN)

CM

OCT 23 2017

OCT 30 2017

RECEIVED