

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St. Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-24754-00-00
Spot: NWNESWNE Sec/Twnshp/Rge: 31-20S-11W
1380 feet from N Section Line, 1665 feet from E Section Line
Lease Name: DUNCAN Well #: 1
County: BARTON Total Vertical Depth: 3456 feet

Operator License No.: 3293
Op Name: RUSSELL OIL, INC.
Address: PO BOX 8050
EDMOND, OK 73083

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3455		135 SX
SURF	8.625	277		230 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/18/2017 8:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIEE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: TODD BROWN Co.mpany: RUSSELL OIL, INC. Phone: (785) 445-6270

Proposed
Plugging
Method:

Ordered 400 sx 60/40 pozmix 4% gel cement w/400 # hulls.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/18/2017 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perforations and topped with 5 sx cement. Cut casing at 2300'. Pulled casing to 1300' and pumped 125 sx cement w/200 # hulls. Pulled casing to 900' and pumped 50 sx cement w/100 # hulls. Pulled casing to 600' and pumped 50 sx cement w/100 # hulls. Pulled casing to 250'. Circulated cement to surface with 125 sx cement. Pulled casing and hole stayed full.

GPS: 38.27180 -098.57740

Perfs:

Top	Bot	Thru	Comments
3376	3378		

Remarks: QUALITY OILWELL CEMENTING

Plugged through: CSG

INVOICED
NOV - 8 2017

District: 04

Signed Bruce Rodie
(TECHNICIAN)

CM

KCC WICHITA

OCT 30 2017

RECEIVED

OCT 19 2017