

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-077-21975-01-00
Spot: SWNENWNE Sec/Twnshp/Rge: 10-34S-5W
500 feet from N Section Line, 1740 feet from E Section Line
Lease Name: MILLER 3405 Well #: 1-10H
County: HARPER Total Vertical Depth: 5572 feet

Operator License No.: <u>34192</u>	String	Size	Depth (ft)	Pulled (ft)	Comments
Op Name: <u>SANDRIDGE EXPLORATION AND PRO</u>	COND	20	110		10 SX
Address: <u>123 ROBERT S. KERR AVE</u>	PROD	7	5572		320 SX
<u>OKLAHOMA CITY, OK 73102</u>	SURF	9.625	583		340 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/19/2017 12:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES Phone: (405) 429-6165

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/21/2017 4:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

A CIBP WAS SET AT 4750' ON TUBING. RELEASED FROM BP & PUMP 180 BBL MUD & 50 SKS CEMENT LAYED OUT TUBING. PULLED & LAYED OUT 1832' OF 7" CASING. RAN TUBING IN HOLE TO 1150' SPOTTED 50 SX CEMENT. PULLED TUBING TO 630' & SPOTTED 50 SX CEMENT. PULLED TUBING TO 300 & CIRCULATED 100 SKS CEMENT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
8367	8621		
8012	8292		
7650	7938		
7290	7586		
6938	7206		
6603	6870		
6207	6502		
5815	6092		
5411	5712		
4091	5098		

Remarks: ORR ENTERPRISES, CLASS C CEMENT. TMD = 8700

Plugged through: TBG

INVOICE
NOV - 2 2017

District: 02

Signed  _____
(TECHNICIAN)