

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-24113-00-00
Spot: SESEWNNE Sec/Twnshp/Rge: 19-6S-24W
1143 feet from N Section Line, 1518 feet from E Section Line
Lease Name: OLSON ODLE Well #: 1
County: GRAHAM Total Vertical Depth: 4400 feet

Operator License No.: 34704
Op Name: SHOESTRING RESOURCES, LLC
Address: 535 S. FULTON
LENORA, KS 67645

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3965		330 SX
SURF	8.625	394		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/20/2017 8:00 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: PRESTON DREILING Company: SHOESTRING RESOURCES, LLC D Phone: (785) 567-3168

Proposed Plugging Method: Ordered 500 sx 60/40 pozmix 4% gel cement and 500 # hulls.
Port Collar at 2190' w/330 sx cement.
Perforations: 3718' - 3722' and 3873' - 3876'.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/20/2017 9:30 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Tied on to casing and pumped 375 sx cement w/250 # hulls. Shut in pressure 400 psi. Tied on to backside and squeezed with 10 sx cement. Shut in pressure 300 psi.
GPS: 39.52036 -100.03664

Perfs:

Top	Bot	Thru	Comments
3873	3876		
3718	3722		

Remarks: QUALITY OIL WELL CEMENTING TICKET # 324

Plugged through: CSG

District: 04

Signed _____

(TECHNICIAN)

CM

KCC WICHITA

OCT 30 2017

RECEIVED

OCT 23 2017

Form CP-2/3

INVOICED
10/19 - 8 3117