

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-02242-00-00
Spot: NW NESW Sec/Twnshp/Rge: 18-14S-13W
2310 feet from S Section Line, 3630 feet from E Section Line
Lease Name: REIN B Well #: 8
County: RUSSELL Total Vertical Depth: 2352 feet

Operator License No.: 6867
Op Name: STEINLE, LA VERN DBA STEINLE OIL
Address: PO EOX 95
BUNKER HILL, KS 67626

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	2346		200 SX
SURF	10	445		125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/14/2017 9:00 AM
Plug Co. License No.: 34071 Plug Co. Name: PATRIOT WELL SERVICE, INC.
Proposal Rcvd. from: TODD DINKEL Company: PATRIOT WELL SERVICE, INC. Phone: (785) 639-5415

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement, 8 sx gel and 600 # hulls.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/14/2017 1:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perforated at 1200' and 825'. Hole in casing at 250' - 260'. Ran tubing to 2250' and pumped 8 sx gel followed by 75 sx cement w/80 # hulls. Pulled tubing to 1275' and pumped 150 sx cement w/240 # hulls. Pulled tubing to 350' and pumped 50 sx cement. Cement circulated to pit. Closed valve. Pumped 25 sx of cement. Circulated cement out of the braden head to the pit. POOH. Topped off casing with 15 sx cement. Cellar stayed full.

GPS: 38.83369 -098.81322

Perfs:

Top	Bot	Thru	Comments
2327	2346		

Remarks: GLOBAL CEMENTING TICKET # 3121

Plugged through: TBG

District: 04

Signed _____

Ray Dinkel

(TECHNICIAN)

CM

KCC WICHITA

Form CP-2/3

OCT 17 2017

RECEIVED

SEP 25 2017