

TO: STATE CORP ORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-199-20443-00-00
Spot: NESWSESW Sec/Twnshp/Rge: 13-13S-38W
335 feet from S Section Line, 1875 feet from W Section Line
Lease Name: BERTRAND TRUST Well #: 1-13
County: WALLACE Total Vertical Depth: 4666 feet

Operator License No.: 6044
Op Name: STELBAR OIL CORPORATION, INC.
Address: 1625 N WATERFRONT PKWY SUITE 2
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	310		210 SX

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 07/26/2017 12:00 AM
Plug Co. License No.: 5142 Plug Co. Name: STERLING DRILLING COMPANY
Proposal Rcvd. from: GARY Company: STERLING DRILLING COMPANY Phone: (620) 672-9508

Proposed Plugging Method: Ordered 255 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: BRUCE RODIE Witness Type: NONE
Date/Time Plugging Completed: 07/26/2017 12:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfs:

1st plug @2395 w/50 sx
2nd plug @1420 w/100 sx
3rd plug @360 w/50 sx
4th plug @40 w'10 sx

Rathole 30 sx Mousehole 15 sx

Remarks: QES

Plugged through: DP

INVOICE

NOV - 5 2017

District: 04

Signed

Bruce Rodie

(TECHNICIAN)

CM

OCT 13 2017

KCC WICHITA

OCT 30 2017

RECEIVED