

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-163-22363-00-00
Spot: W2NWSWSE Sec/Twnshp/Rge: 18-7S-17W
990 feet from S Section Line, 2321 feet from E Section Line
Lease Name: ROGERS Well #: A-1
County: ROOKS Total Vertical Depth: 3303 feet

Operator License No.: 32278

String Size Depth (ft) Pulled (ft) Comments

Op Name: TENGASCO, INC.

PROD 5.5 3295 125 SX

Address: 1327 NOOSE RD PO BOX 458
HAYS, KS 67601

SURF 8.625 1342 535 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 10/13/2017 8:30 AM

Plug Co. License No.: 32332

Plug Co. Name: FISCHER WELL SERVICE, INC.

Proposal Rcvd. from: GARY WAGNER

Company: TENGASCO, INC.

Phone: (785) 625-6374

Proposed Plugging Method: Ordered 500 sx 60/40 pozmix 4% gel cement w/600 # hulls and 9 sx gel.
Perforate 2 holes at 1300'.
High fluid level, will run tubing to plug.

Plugging Proposal Received By: RICHARD WILLIAMS

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 10/13/2017 12:45 PM

KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perforated 2 holes at 1300'. Ran tubing to 3219'. Quality Oil Well Cementing pumped 9 sx gel followed by 75 sx cement w/300 # hulls. Pulled tubing to 1610' and pumped 75 sx cement w/200 # hulls. Pulled tubing to 1021' and pumped 120 sx cement. Circulated cement out 5 1/2" casing. PTOH. Hooked up to 5 1/2" casing and pumped 140 sx cement down casing. Circulated cement out 8 5/8" surface casing. Both casings full of cement at surface.

Perfs:

Top	Bot	Thru	Comments
3295	3296		
3075	3078		
3060	3062		
2978	2981		
2883	2887		

Remarks:

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

KCC WICHITA

OCT 17 2017

OCT 30 2017

RECEIVED

Form CP-2/3

NOV 01 2017

NOV - 9 2017