

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-22312-00-00
Spot: SWNW Sec/Twnshp/Rge: 5-11S-18W
3300 feet from S Section Line, 4620 feet from E Section Line
Lease Name: SALINE RIVER GRAZING Well #: 3
County: ELLIS Total Vertical Depth: 3565 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3562		175 SX
SURF	8.625	170		130 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/10/2017 9:00 AM
Plug Co. License No.: 34044 Plug Co. Name: JD'S WELL SERVICE INC.
Proposal Rcvd. from: KEN BUHLER Company: TRANS PACIFIC OIL CORPORATIO Phone: (785) 483-1821

Proposed Plugging Method: Ordered 250 sx 60/40 pozmix 4% gel cement, 6 sx gel and 500 # hulls.
Perforations: 3436' 3509' - OA
CIBP set over Arbuckle
CIBP set at 3290' over KC perfs.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/10/2017 1:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perfs:

E.L.I. Wireline Service perforated at 1850', 1409' and 800'. JD's ran in hole with tubing to 3250'. Quality rigged to tubing and pumped 6 sx gel followed by 50 sx cement w/250 # hulls mixed in. Pulled tubing to 1850' and pumped 135 sx cement w/150 # hulls mixed in to circulate cement up 4 1/2" casing. Pulled tubing. Rigged to 4 1/2" casing and pumped 15 sx cement w/200 psi. Shut in pressure 200 psi. Rigged to 8 5/8" surface casing with instant pressure. Pumped 1/2 bbl cement.

GPS: 39.12645 -099.34916


Remarks: QUALITY CEMENTING CO. TICKET # 315

Plugged through: TBG

INVOICE
10/10/17

District: 04

Signed _____



(TECHNICIAN)

CM

KCC WICHITA

OCT 30 2017

RECEIVED

Form CP-2/3

OCT 13 2017