

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-073-19668-00-00
Spot: SWNENWNE Sec/Twnshp/Rge: 26-24S-12E
530 feet from N Section Line, 3465 feet from W Section Line
Lease Name: LANE Well #: 2
County: GREENWOOD Total Vertical Depth: 1715 feet

Operator License No.: 32044
Op Name: TRIMBLE & MACLASKEY OIL LLC
Address: 110 SOUTH ST PO BOX 171
GRIDLEY, KS 66852

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	1701	---	20 SX
SURF	8.625	113	---	65 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/29/2017 9:00 AM
Plug Co. License No.: 32044 Plug Co. Name: TRIMBLE & MACLASKEY OIL LLC
Proposal Rcvd. from: TRIMBLE & MACLASKEY Company: _____ Phone: (620) 836-2000

Proposed Plugging Method: Perf at 450ft and 250ft, cement plug on bottom, cement plug at 450ft, cement plug at 250ft circulate to surface

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: NONE
Date/Time Plugging Completed: 09/29/2017 1:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

ran tubing to 1630', pumped 25 sxs cement, pulled tubing to 450', pumped 20 sxs cement, pulled tubing to 250', pumped 75 sxs cement to surface, shot casing @ 450' & 250', gel spacers between cement plugs.

Perfs:

RECEIVED
KCC DIST # 3
OCT 24 2017
CHANUTE, KS

mt

INVOICE
10/11 - 9 2017

Remarks:

Plugged through: TBG

District: 03

Signed M. Heffern
(TECHNICIAN)

810 E 7TH
 PO Box 92
 EUREKA, KS 67045
 (620) 583-5561



Cement or Acid Field Report
 Ticket No. 3524
 Foreman Steve Neal
 Camp EurekaKs

APZ 15-073-19668

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
9-29-17	1000	LANE #2	26	24S	12E	Greenwood	KS
Customer			Unit #	Driver	Unit #	Driver	
Trimble & MacLuskey			102	Rick			
Mailing Address			113	Tasen			
P.O. Box 171			145	Alan			
City	State	Zip Code					
Gridley	Ks	66852					

Job Type Pit. old well Hole Depth 1715 Slurry Vol. _____ Tubing _____
 Casing Depth 1701 Hole Size _____ Slurry Wt. _____ Drill Pipe _____
 Casing Size & Wt. 5 1/2 Cement Left in Casing _____ Water Gal/SK _____ Other _____
 Displacement _____ Displacement PSI _____ Bump Plug to _____ BPM _____

Remarks: Safety Meeting: Plug well as follow, Pump 250^{ft} Gel Flush ahead.
Spot 25 SKS AT 1680'
Spot 20 SKS AT 450
75 SKS 250 TO SURFACE
Total 120 SKS 60/40 Perm Cement 4% Gel

Thank You

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C105	1	Pump Charge	750.00	750.00
C107	30	Mileage	3.95	118.50
C203	120 SKS	60/40 Perm Cement	12.75	1530.00
C206	400 ^{gals}	Gel 4%	.20	80.00
C206	250 ^{gals}	Gel Flush	.20	50.00
C108A	3 1/2 hrs	Ten Mileage Bulk Truck	MLK	345.00
C113	3 hrs	Sobbi Ucc Truck	85.00	255.00
			Sub Total	3128.50
			7.50% Sales Tax	234.64
Authorization Witness by <u>Brian</u> Title <u>Co. Rep</u>			Total	3363.14

INVOICED
 10/1 - 9/2017

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.