

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-205-23938-00-00
Spot: NENESWNE Sec/Twnshp/Rge: 12-29S-14E
3837 feet from S Section Line, 1504 feet from E Section Line
Lease Name: BERCKEFELDT Well #: 26
County: WILSON Total Vertical Depth: 1130 feet

Operator License No.: 34697
Op Name: WILSON COUNTY HOLDINGS LLC
Address: 1135 N. 15TH ST.
FREDONIA, KS 66736

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.375	1120		120 SX
SURF	5	40		12 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/14/2016 12:00 PM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Rcvd. from: FORREST SUTHERLAND Company: WILSON COUNTY HOLDINGS Phone: (620) 325-4344

Proposed Plugging Method: Run 1" pipe to TD of well and pump cement to surface. Trip out and top well off then cut below plow depth.

Plugging Proposal Received By: ALAN DUNNING Witness Type: NONE
Date/Time Plugging Completed: 12/14/2016 12:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

Perfs:

A 1 inch cement string was lowered to TD. Begin pumping cement, but did not get circulation. The cement string was pulled. The next day the 1 inch cement string was lowered to 400 ft where the cement was tagged. The well was then pumped full of cement. A total of 77 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

RECEIVED
KCC DIST # 3
OCT 12 2017
CHANUTE, KS

AD

Remarks:

Plugged through: CSG

District: 03

Signed Alan Dunning
(TECHNICIAN)