

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-205-23801-00-00  
Spot: NWNWNE Sec/Twnshp/Rge: 12-29S-14E  
5103 feet from S Section Line, 1288 feet from E Section Line  
Lease Name: BERCKFELDT Well #: 22  
County: WILSON Total Vertical Depth: 1130 feet

Operator License No.: 34697  
Op Name: WILSON COUNTY HOLDINGS LLC  
Address: 1135 N. 15TH ST.  
FREDONIA, KS 66736

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4	1115		122 SX
PROD	2.5	1120		258 SX
SURF	7	25		10 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/15/2016 12:00 PM  
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC  
Proposal Rcvd. from: FORREST SUTHERLAND Company: WILSON COUNTY HOLDINGS Phone: (620) 325-4344

Proposed Plugging Method: Run pipe to TD of well and pump cement to surface. Remove plugging string and top well off then cut off below plow depth.

Plugging Proposal Received By: ALAN DUNNING WitnessType: NONE  
Date/Time Plugging Completed: 11/15/2016 12:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

Perfs:

The 2.875 inch longstring was hooked onto directly. Circulation was established by pumping 5 bbls of water. The well was then pumped full of cement containing cottonseed hulls by squeezing. The well was shut in with 700 psi. A total of 42 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

RECEIVED  
KCC DIST # 3  
OCT 12 2017  
CHANUTE, KS

AD

INVOICED

11/15/2016

Remarks:

Plugged through: CSG

District: 03

Signed Alan Dunning  
(TECHNICIAN)