

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION nw-nw-nw

SEC. 12 TWP. 11 RGE. 13w

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Hoffman "B"

Operator Petroleum, Inc. Address 314 Norby Bldg - Wichita - Kans.

Field _____ County Stafford

Total Depth 3704 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/8 - 321 ft - Circulated with cement.
5 1/2" casing set at 366 ft - Plugged back to 3436 ft
with mud & Lane Wells Plug - Filled with chat
from 3436 ft to 3400 ft - Dumped 3 sacks of
cement in the 5 1/2" casing at 3400 ft - Shot off &
Pulled the 5 1/2" casing - Filled with mud to 320 ft -
Rock Bridge & 15 sacks of cement at 320 ft - mud
to 30 ft - Plug & 10 sacks of cement at the surface

on Div.

MAR 7 X 1950 3-7-50

S. _____
District Conservation Agent

Date 3-4-50

PLUGGING
FILE SEC 28 T 11 R 13w
BOOK PAGE 141 LINE 25