

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION 2w-2w-2E

SEC. 22 TWP. 21 RGE. 13w

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease J. Hoffman

Operator Petroleum, Inc. Address 314 Newby Bldg. Wichita, Kans

Field _____ County Stafford

Total Depth 3676 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 3/4 - 250 ft. Circulated with cement.
4 1/2" casing at 3640 ft. Plugged back to 3540 ft
with chert - Dumped 3 sacks of cement
at 3640 ft. Shot off & pulled the 4 1/2" casing.
Filled with sand to 250 ft. Rock Bridge & 15 sacks
of cement at 250 ft. Mud to 30 ft - Plug
& 10 sacks of cement at the surface

MAR 11 1950

3-11-50

CORPORATION
COMMISSION
KANSAS

C. H. Stough
District Conservation Agent

Date 3-9-50

PLUGGING
FILE SEC 22T 21R 13w
BOOK PAGE 14 LINE 14