

15.185.10643.0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wich. Mo, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER N/A

LEASE NAME Fanshies

WELL NUMBER 1

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 25 TWP. 21 RGE. 13 (E) or (W)

COUNTY Stafford

Date Well Completed

Plugging Commenced 2-5-92

Plugging Completed 2-21-92

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Nadel & Gussman

ADDRESS 3200 First Natl Twr Tulsa, OK. 74103

PHONE#(918) 583-3333 OPERATORS LICENSE NO. 5337

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3622'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	325'	none
				5 1/2"	3620'	1208'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Sanded bottom to 3600' ran 5 sacks cement. Shot pipe @3093', 3012', 2901', pipe parted. Plugged with 3 hulls, 10 gel, 50 cement, 10 gel, 2 hulls, 125 sacks cement 60/40 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Kelso Casing Pulling, Inc. STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well, and that the same are true and correct, so help me God.


(Signature) Mike Kelso

(Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 25 day of February, 19 92

Irene Herzberg
Notary Public

My Commission Expires:



RESERVE DRILLING COMPANY

FANSHIER No. 1 SESE NW 25-21-13W
Stafford County, Kansas

Comm. 1-16-49
Comp. 1-30-49

Casing Record:

8-5/8" @ 325' 200 sax
5-1/2" @ 3620' 100 sax

FORMATION

Sand	41	
Sand and gravel	220	20
Red bed	325	
Shale	625	
Shale and shells	670	
Anhydrite	705	
Shale and shells	1575	
Shale and lime	1670	
Lime	1840	
Broken Lime	1950	
Shale and lime	2340	
Shale and shells	2655	
Shale	2665	
Shale and Lime	2865	
Lime	3179	
Shale and Lime	3242	
Lime	3478	
Shale	3517	
Viola Lime	3561	
Shale	3563	
Shale and lime	3620	
Arbuckle Limestone	3622	T.D.

RECEIVED
KANSAS CORPORATION COMMISSION

JAN 27 1992

CONSERVATION DIVISION
WICHITA, KS

STATE OF KANSAS

COUNTY OF SEDGWICK

} SS:

L. C. Hay, being first duly sworn on his oath states that the above formations and depths are correct as taken from the Daily drilling report.

Subscribed and sworn to before me this 2nd day of February, 1949.

My commission expires Nov. 3, 1952

L. C. Hay
Notary Public