

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-10652-0000

LEASE NAME Fischer

WELL NUMBER B-3

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 25 TWP. 21 RGE. 13W (E) or (W)

COUNTY Stafford

Date Well Completed

Plugging Commenced 3-27-92

Plugging Completed 4-1-92

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Nadel & Gussman

ADDRESS 3200 First Natl Twr Tulsa, Ok. 74103

PHONE# (918) 583-3333 OPERATORS LICENSE NO. 5337

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by Duane Rankin (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3630'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	300'	none
				5 1/2"	3627'	307'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Sanded bottom to 3570' ran 5 sacks cement. Shot pipe @2595' pipe parted.
Pumped 50 cement w/50 lbs of hulls mixed in, 10 gel, w/50 lbs. hulls mixed
in 100 lbs. of hulls for spacer then 200 sacks of cement 60/40 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. RECEIVED
STATE CORPORATION COMMISSION
License No. 6050

Address P.O. Box 347 Chase, Kansas 67524 APR 03 1992

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Nadel & Gussman CONSERVATION DIVISION
Wichita, Kansas

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 2 day of April, 19 92

Irene Herzberg
Notary Public

My Commission Expires:



WELL LOG

NADEL AND GUSSMAN

FISCHER B-3

NE SW SE 25-21-13W
Stafford County, Kansas

Comm. 10-26-49

Comp. 11-7-49

Casing: 8-5/8" 300' 210 Sax
5-1/2" 3627' 125 Sax

Elevation 1878

RECEIVED
STATE CORPORATION COMMISSION

NOV 20 1949
CONSERVATION DIV
WICHITA, KANSAS

Formation	Depth
Sand	230
Red Bed and shale	300
Red Bed and shale	700
Anhydrite	735
Shale and shells	1600
Shale and lime	1705
Broken lime	1865
Shale and lime	2110
Shale and shells	2175
Broken lime	2255
Shale and shells	2535
Shale and lime	2555
Broken lime	2650
Shale and lime	2955
Lime	3025
Shale and lime	3110
Lime	3592
Shale	3627
Lime	3630 T.D.

Tops

Lansing-K.C.	3300
Viola	3534
Simpson	3588
Arbuckle	3627

STATE OF KANSAS

SS:

COUNTY OF SEDGWICK

L. C. Hay, of lawful age, being first duly sworn, states that the above formations and depths are true and correct according to the daily drilling log on the Fischer B-3 in the NE SW SE 25-21-13W, Stafford County, Kansas.

L. C. Hay

Subscribed and sworn to before me this 19th day of November, 1949.

Paul Babby

My commission expires Nov. 3, 1952