

STATE OF KANSAS STATE CORPORATION COMMISSION 200 Colorado Derby Bldg. Wichita, Kansas 67202


OCT 01 1982

CONSERVATION DIVISION Wichita, Kansas

WELL PLUGGING RECORD

Give All Information Completely Make Required Affidavit

COUNTY Stafford SEC. 25 TWP. 21S RGE. 13W SW NE SE



Lease Owner Nadel and Gussman Lease Name FISCHER Well No. B-5 Office Address 3232 First National Tower-Tulsa, OK 74103 Character of Well (Completed as Oil, Gas or Dry Hole): oil Date Well Completed 9/6/51 Application for plugging filed 8/13/82 Plugging commenced 9/8/82 Plugging completed 9/8/82 Reason for abandonment of well or producing formation Depleted

Locate Well correctly on above Section Platt.

Was permission obtained from the Conservation Division or it's Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well J. H. Metz

Producing formation Arbuckle Depth to top 3673 bottom 3678 T.D. 3685

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Table with 7 columns: Formation, Content, From, To, Size, Put in, Pulled Out. Row 1: Arbuckle, Oil, 3673, 3678, 8-5/8", 295', none. Row 2: (depleted), 5-1/2", 3675', none.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

200 sacks of 50/50 Poz and 3% Calcium Chloride was pumped down 5-1/2" and 8-5/8" annulus at the same time. Shutin pressure 400#.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Allied Cementing Company(Russell, Ks.)

STATE OF Oklahoma COUNTY OF Tulsa, ss.

M. R. Taylor, Mgr. of Production (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) M R Taylor 3232 First National Tower-Tulsa, OK 74103 (Address)

SUBSCRIBED AND SWORN TO before me this 28th day of September, 19 82

Mildred Carter Notary Public.

My Commission expires: 5/11/83

WELL LOG

NADEL AND GUSSMAN

FISCHER B No. 5

SW NE SE 25-21-13W
Stafford County, Kans.

Comm. 8-18-51
Comp. 9- 2-51

Casing: 8-5/8" @ 295' W/200 sax
5-1/2" @ 3675' W/100 sax

Formation	Depth
Surface	295
Red bed and shale	665
Anhydrite	820
Shale and shells	1460
Broken Lime	1560
Lime and shale	2200
Shale and shells	2485
Shale	2515
Shale and shells	2740
Shale	2755
Shells	2780
Shale and lime	2845
Lime	2940
Shale and lime	3005
Shale	3030
Lime	3110
Shale and lime	3270
Shale	3292
Lime	3536
Lime and shale	3638
Lime	3644

GEOLOGICAL TOPS - Corrected

Brown Lansing	3302
White Lansing	3318
Conglomerate	3562
Simpson shale	3654
Arbuckle	3673

Corrected T.D. According to
Drill Pipe and Schlumberger
measurements 3678

RECEIVED
STATE CONSERVATION COMMISSION
AUG 16 1982
CONSERVATION DIVISION
Wichita, Kansas

A.C.H.

STATE OF KANSAS)
) SS:
COUNTY OF SEDGWICK)

L. C. Hay, of lawful age, deposes and states that the above forma-
tions and depths are true and correct as taken from the daily drilling
log of the Fischer B No. 5 in the SW NE SE 25-21-13W, Stafford County,
Kansas.

Subscribed and sworn to before me this 6th day of September, 1951.

L. C. Hay
Notary Public

My comm. expires Nov. 3, 1952