

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15.185.10656.0000

API NUMBER N/A

LEASE NAME FISCHER

WELL NUMBER B-7

SPOT LOCATION NW NW SE

SEC. 25 TWP. 21 SRGE. 13 (N) or (W)

COUNTY Stafford

Date Well Completed 2-21-52

Plugging Commenced 10-14-87

Plugging Completed 10-14-87

LEASE OPERATOR Nadel and Gussman

ADDRESS 3232 First National Tower - Tulsa, OK 74103

PHONE # (918) 583-3333 OPERATORS LICENSE NO. 5337

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District #1, Dodge City

Is ACO-1 filed? N/A If not, is well log attached? Yes

Producing formation Lansing-K.C. Depth to top 3468' bottom 3474' T.D. 3611'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Lansing-K.C.	Oil & water	3468	3474	8-5/8"	349'	None
				5-1/2"	3620'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Mixed 150 sacks ATL cement w/200# hulls-pumped down 5-1/2" casing @ 100# pressure; Mixed 100 sacks with 100# hulls - pumped down 8-5/8" casing @ 500# max. pressure and 200# SIP/ Total cement used 300 sacks.

Witnessed by state plugger Duane Rankin

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Company, Inc. License No. Not required

Address Box 31 - Russell, Kansas 67665

STATE OF OKLAHOMA COUNTY OF TULSA, ss.

M. R. Taylor, Manager of Production (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) M. R. Taylor
3232 First National Tower

(Address) Tulsa, OK 74103

RECEIVED
STATE CORPORATION COMMISSION

SUBSCRIBED AND SWORN TO before me this 20 day of Oct., 1987

OCT 22 1987

Mildred Carter
Notary Public

My Commission expires: May 11, 1991 CONSERVATION DIVISION
WICHITA, KANSAS

15.185.10656.0000

WELL LOG

NADEL AND GUSSMAN

FISCHER B-7

NW SE 25-21-13W
Stafford County, Kansas

Comm: 2-11-52

Comp: 2-21-52

Casing: 8-5/8" 349' w/300 sax
5-1/2" 3620' w/150 sax

Formations	Depth
Sand, gravel	270
Red bed and shale	347
Red bed and shells	696
Anhydrite	730
Red bed, shale and shells	1190
Shale and salt	1255
Shale and shells	1555
Lime and shale	1825
Lime (broken)	1920
Shale and lime	1950
Broken lime	2140
Shale and lime shells	2360
Shale and shells	2560
Broken lime	2633
Shale and lime shells	2770
Lime	2880
Lime and shale	3080
Lime	3156
Lime and shale	3195
Lime	3270
Shale	3277
Lime	3495
Shale and lime	3519
Lime and chert	3551
Shale	3560
Shale and lime	3610

GEOLOGICAL TOPS

Heebner Shale	3137
Brown Lime	3260
Lansing	3281
Viola	3519
Simpson shale	3556
Arbuckle	3605-3610

K.C. 45

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS:

L. C. Hay, of lawful age, deposes and states that the above formations and depths are correct as shown by the daily drilling log of the Fischer B No. 7 well in the NW SE 25-21-13W, Stafford County, Kansas.

L. C. Hay

Subscribed and sworn to before me this 25th day of February, 1952.

Paul Bass

Notary Public

My commission expires Nov. 3, 1952

WELL LOG

NADEL AND GUSSMAN

FISCHER B-7

NW SE 25-21-13W
Stafford County, Kansas

Comm: 2-11-52
Comp: 2-21-52

Casing: 8-5/8" 349' w/300 sax
5-1/2" 3620' w/150 sax

Formations	Depth
Sand, gravel	270
Red bed and shale	347
Red bed and shells	696
Anhydrite	730
Red bed, shale and shells	1190
Shale and salt	1255
Shale and shells	1555
Lime and shale	1825
Lime (broken)	1920
Shale and lime	1950
Broken lime	2140
Shale and lime shells	2360
Shale and shells	2560
Broken lime	2633
Shale and lime shells	2770
Lime	2880
Lime and shale	3080
Lime	3156
Lime and shale	3195
Lime	3270
Shale	3277
Lime	3495
Shale and lime	3519
Lime and chert	3551
Shale	3560
Shale and lime	3610

GEOLOGICAL TOPS

Heebner Shale	3137
Brown Lime	3260
Lansing	3281
Viola	3519
Simpson shale	3556
Arbuckle	3605-3610

K.C. 43

STATE OF KANSAS)
(SS:
COUNTY OF SEDGWICK)

L. C. Hay, of lawful age, deposes and states that the above formations and depths are correct as shown by the daily drilling log of the Fischer B No. 7 well in the NW SE 25-21-13W, Stafford County, Kansas.

L. C. Hay

Subscribed and sworn to before me this 25th day of February, 1952.

Paul B...
Notary Public

My commission expires Nov. 3, 1952

OCT 22 1987