

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15.185.10646.0000

API NUMBER N/A

LEASE NAME FANSHIER

WELL NUMBER 4

SPOT LOCATION SW SE NW

SEC ²⁵24 TWP 21S RGE 13W (W)

COUNTY Stafford

Date Well Completed 10/16/51

Plugging Commenced 8/21/85

Plugging Completed 8/21/85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Nadel and Gussman

ADDRESS 3232 First National Tower - Tulsa, OK 74103

PHONE #(918) 583-3333 OPERATORS LICENSE NO. 5337

Character of Well oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? District #1, Dodge City

Is ACO-1 filed? N/A If not, is well log attached? yes

Producing formation Lansing K.C. Depth to top 3456 bottom 3465 T.D. 3627

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Lansing K.C.</u>	<u>oil & water</u>	<u>3456</u>	<u>65</u>	<u>8-5/8"</u>	<u>302'</u>	<u>none</u>
				<u>5-1/2"</u>	<u>3625 1/2</u>	<u>none</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. one (1) sack hulls and 50 sks 60-40 Poz with 6% gel plus 75 sks gel plus 100 sks 60-40 Poz with 6% gel down 5 1/2" casing; 400# Max. SIP 200#; 125 sks 60-40 Poz with 6% gel down 8-5/8" - 5 1/2" annulus; 400# Max. 250# SIP
Witnessed by state plugger, J. H. Metz

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co. License No. _____
Address Box 31 - Russell, Ks 67665

STATE OF Oklahoma COUNTY OF Tulsa, ss.

RECEIVED
STATE CORPORATION COMMISSION

M. R. Taylor, Mgr. of Production (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

AUG 28 1985

CONSERVATION DIVISION
Wichita, Kansas

(Signature) MR Taylor
(Address) 3232 First National Tower
Tulsa, OK 74103

SUBSCRIBED AND SWORN TO before me this 26 day of August, 19 85

My Commission expires: 5/11/87

Mildred Carter
Notary Public

