

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION FORM CP-4
Rev. 12-15-80


SFP 3 1982

CONSERVATION DIVISION
Wichita, Kansas

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Stafford SEC. 25 TWP. 21S RGE. 13 W
Location as in quarters or footage from lines:
NW SE NW



Lease Owner Nadel and Gussman
Lease Name FANSHIER Well No. 3
Office Address 3232 First National Tower-Tulsa, OK 74103
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed 10/12/49
Application for plugging filed 7/2/82
Plugging commenced 8/18/82
Plugging completed 8/18/82
Reason for abandonment of well or producing formation Depleted

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well J. H. Metz

Producing formation Arbuckle Depth to top 3674 bottom 3682 T.D. 3682

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
Arbuckle	oil	3674	3682			
				8-5/8"	322'	none
				5-1/2"	3674'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mixed 200 sacks of 50/50 Poz with 3 sacks hulls, 4% gel and 3% CaCl and pumped down 8-5/8" and 5-1/2" annulus at same time. Maximum pressure 100#

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Allied Cementing Co. Inc. (Russell, Ks.)

STATE OF OKLAHOMA COUNTY OF TULSA, ss.

M. R. Taylor, Mgr. of Production (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) MR Taylor
3232 First National Tower-Tulsa, OK 74103
(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of August, 19 82

Mildred Carter
Mildred Carter Notary Public.

My Commission expires: 5/11/83

WELL LOG

MADDELL AND GUSSMAN

FANSHIER No. 3

NW SE NW 25-21-13W
Stafford County, Kansas

Date Commenced - 9-30-49
Date Completed - 10-12-49

Casing:
8-5/8" 322' 210 Sax
5 1/2" 3674' 125' Sax

Formations

Sand and gravel	210
Sand and Pyrite	322
Shale and Red Bed	705
Anhydrite	735
Shale and shells	1645
Lime	1710
Broken Lime	1945
Lime	2060
Shale and Lime	2220
Lime	2305
Shale and Lime	2330
Shale and Shells	2785
Shale and Lime	2940
Lime	3555
Shale and Lime	3640
Shale and sand	3670
Shale and Lime	3677
Arbuckle Limestone	3682-T.D.

Geological Tops

Lansing	3317
Viola	3556
Simpson	3613
Arbuckle	3674

RECEIVED
STATE CORPORATION COMMISSION
JUL 6 1982
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS:

L. C. Hay, of lawful age, being first duly sworn on oath states that the above formations and depths are true and correct as taken from the daily drilling log of the Fanshier Well #3 located in the NW SE NW 25-21-13W, Stafford County, Kansas.

L. C. Hay

Subscribed and sworn to before me this 19th day of October, 1949.

Notary Public
Notary Public

My commission expires Nov. 3, 1952