

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15.185.10664.0000

API NUMBER N/A

LEASE NAME Fischer

WELL NUMBER D-7

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 25 TWP. 21S RGE. 13W ~~KEX~~or (W)

COUNTY Stafford

Date Well Completed

Plugging Commenced 3-16-92

Plugging Completed 4-1-92

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Nadel & Gussman

ADDRESS 3200 National Twr Tulsa, Ok. 74103

PHONE# (918) 583-3333 OPERATORS LICENSE NO. 5337

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by Duane Rankin (KCC District Agent's Name).

Is ACO-1 filled? If not, Is well log attached?

Producing Formation Depth to Top Bottom T.D. 3620'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	349'	none
				5 1/2"	3619'	2776'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
 Sanded bottom to 3318' ran 5 sacks cement. Shot pipe @3000', 2900', 2776'.
 Pumped 300# of hulls, 10 gel, 50 cement, 10 gel, 100# of hulls and 100 sacks of cement 60/40 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

RECEIVED
 STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Kelso Casing Pulling, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator Wichita, Kansas) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 2 day of April, 19 92

My Commission Expires:

Notary Public
 IRVINE HERZBERG
 My Appt. Exp. Aug. 24, 1993

CONSERVATION DIVISION

APR 6 1992

WELL LOG

NADEL AND GUSMAN

FISCHER D No. 7

NE NE SW 25-21-13W
Stafford County, Kans.

Comm. 1-31-52
Comp. 2-10-52

Casing: 8-5/8" 349' w/300 Sax
5-1/2" 3619' w/100 Sax

Formations	Feet
Sand, gravel and shale	250
Red bed and shells	694
Anhydrite	735
Red bed, shale and shells	800
Red bed and shale	1030
Shale and shells	1560
Lime and shale	1650
Broken Lime	1790
Broken lime and shale	1910
Broken lime	2030
Shale and lime	2113
Shale and shells	2700
Shale and lime	2800
Shale and shells	2930
Broken lime	3025
Lime and shale	3341
Lime	3500
Lime and chert	3558
Shale	3564
Shale and lime	3611
Arbuckle	3620

RECEIVED
STATE CORPORATION COMMISSION

FEB 20 1952
CONSERVATION DIVISION
WICHITA, KANSAS

GEOLOGICAL TOPS

Heebner Shale	3135
Brown Lime	3262
Lansing-Kansas City	3280
Viola	3522
Simpson Shale	3556
Arbuckle	3518-20

STATE OF KANSAS }
COUNTY OF SEDGWICK } SS:

L. C. Hay, of lawful age, deposes and states that the above formations and depths are correct as shown by the daily drilling log of the Fischer D No. 7 in the NE NE SW 25-21-13W, Stafford County, Kansas.

L. C. Hay

Subscribed and sworn to before me this 13th day of February, 1952.

Walter B. Bess
Notary Public

My commission expires Nov. 3, 1952