

15.185.10660.0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

RECEIVED Form CP-4  
STATE CORPORATION COMMISSION Rev. 12-15-80

SFP 3 1982

CONSERVATION DIVISION  
Wichita, Kansas

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Stafford SEC. 25 TWP. 21S RGE. 13 SW  
Location as in quarters or footage from lines:  
SE NW SW

		25	

Lease Owner Nadel and Gussman  
Lease Name FISCHER Well No. D-2  
Office Address 3232 First National Tower-Tulsa, OK 74103  
Character of Well (Completed as Oil, Gas or Dry Hole): \_\_\_\_\_  
Date Well Completed 1/14/49  
Application for plugging filed 7/2/82  
Plugging commenced 8/18/82  
Plugging completed 8/18/82  
Reason for abandonment of well or producing formation Depleted

Locate Well  
correctly on above  
Section Platt.

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well J. H. Metz

Producing formation Arbuckle Depth to top 3619 bottom 3623 T.D. 3623

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
Arbuckle	oil	3619	3623			
				8-5/8"	319'	none
				5-1/2"	3619'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mixed 1 sack hulls with 200 sacks of 50/50 Poz, 4% Gel, 3% CaCl and pumped down 8-5/8" and 5-1/2" annulus at same time. Maximum pressure 100#; shut in at 50#.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Allied Cementing Co. Inc. (Russell, Ks.)

STATE OF OKLAHOM COUNTY OF TULSA, ss.

M. R. Taylor, Mgr. of Production (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) M R Taylor  
3232 First National Tower-Tulsa, OK 74103  
(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of August, 1982

Mildred Carter  
Mildred Carter Notary Public.

My Commission expires: 5/11/83

WELL LOG

15.185.10660.0000

Madel and Gussman  
Tulsa, Oklahoma

Fischer # "D" 2

SE NW SW 25-21-13W  
Stafford County  
Kansas

Date Comm. 1-1-49  
Date Comp. 1-14-49

319' 8-5/8"  
cemented 200 sax  
3620' 5 1/2"  
cemented --

Formation	Time
Sand and gravel	222
Red Bed	325
Sand shale and shells	700
Anhydrite	735
Shale and shells	1730
Broken Lime	1975
Shale and Lime	2105
Shale and shells	2840
Lime	3185
Shale and Lime	3338
Lime	3532
Viola Lime	3572
Lime	3620
Arbuckle	3622 T.D.

State of Kansas )  
Sedgwick County ) SS

L. C. Hay being first duly sworn on oath deposes and states that the above formations are true and correct as taken from the daily drilling report on the above described well.

L. C. Hay

Subscribed and sworn to before me this 15th day of January, 1949.

Nola Boob  
Notary Public

My commission expires Nov. 3, 1952

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 6 1982  
CORPORATION DIVISION  
Wichita Kansas