

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15.185.10663.0000

API NUMBER N/A

LEASE NAME FISCHER

WELL NUMBER D-6

SPOT LOCATION SW NE SW

SEC. 25 TWP. 21S RGE. 13W COR. (W)

COUNTY Stafford

Date Well Completed 1/30/52

Plugging Commenced 8/21/85

Plugging Completed 8/21/85

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Nadel and Gussman

ADDRESS 3232 First National Tower - Tulsa, OK 74103

PHONE # (918) 583-3333 OPERATORS LICENSE NO. 5337

Character of Well oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? District #1, Dodge City

Is ACO-1 filed? N/A If not, is well log attached? yes

Producing formation Lansing K.C. Depth to top 3444 bottom 3450 T.D. 3616

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Lansing K.C.	oil & water	3444	50	8-5/8"	349'	none
				5-1/2"	3613'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. 200 sks 60-40 Poz with 6% gel down 5 1/2" casing; max. pressure 400# SIP 200# 125 sks 60-40 Poz with 6% gel down 8-5/8" - 5 1/2" annulus; 500# max. 250# SIP

Witnessed by state plugger, J. H. Metz

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co. License No. _____
Address Box 31 - Russell, Ks 67665

STATE OF Oklahoma COUNTY OF Tulsa, ss.

M. R. Taylor, Mgr. of Prod. (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) MR Taylor
3232 First National Tower
(Address) Tulsa, OK 74103

SUBSCRIBED AND SWORN TO before me this 26 day of August, 1985

RECEIVED
M. R. Taylor
Notary Public

My Commission expires: 5/11/87

AUG 28 1985

CONSERVATION DIVISION
Wichita, Kansas

Form CP-4
Revised 01-84

WELL LOG

NADEL AND GUSSMAN

FISCHER D No. 6

SW NE SW 25-21-13W
Stafford County, Kans.

Comm: 1-17-52
Comp. 1-30-52

Casing: 8-5/8" 349' w/300 sax
5-1/2" 3613' w/150 sax

Formations	Depth
Sand and gravel	260
Red bed and shale	350
Red bed and shells	670
Red bed	696
Anhydrite	735
Red bed, shale and shells	1485
Shale	1635
Broken Lime	1775
Broken lime and shale	1885
Lime and shale	1968
Shale and shells	2310
Shale	2440
Shale and shells	2620
Shale and lime	2875
Broken lime	2965
Lime and shale	3290
Lime	3478
Lime and shale	3563
Shale	3612
Lime	3616

GEOLOGICAL TOPS

Heebner Shale	3138
Brown Lans.	3263
Lensing-K.C.	3281
Viola	3521
Simpson Shale	3586
Artuckle	3612

STATE OF KANSAS)
) SS:
COUNTY OF SEDGWICK)

L. C. Hay, of lawful age, deposes and states that the above formations and depths are correct as shown by the daily drilling log of the Fischer D No. 6 in the SW NE SW 25-21-13W, Stafford County, Kansas.

L. C. Hay

Subscribed and sworn to before me this 5th day of February, 1952.

My commission expires 11-3-52

W. B. B...
Notary Public

RECEIVED
STATE CORPORATION COMMISSION

AUG 28 1955