

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
Form CP-4
OCT 01 1982 Rev. 12-15-80
CONSERVATION DIVISION
Wichita, Kansas

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Stafford SEC. 25 TWP. 21S RGE. 13W ~~E/W~~
Location as in quarters or footage from lines:
NW SW SW

Lease Owner Nadel and Gussman
Lease Name FISCHER Well No. E-2
Office Address 3232 First National Tower-Tulsa, OK 74103
Character of Well (Completed as Oil, Gas or Dry Hole): oil
Date Well Completed 10/30/51
Application for plugging filed 8/13/82
Plugging commenced 9/8/82
Plugging completed 9/8/82
Reason for abandonment of well or producing formation Depleted

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well J. H. Metz

Producing formation Arbuckle Depth to top 3635 bottom 3638 T.D. 3640

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
<u>Arbuckle</u>	<u>oil (depleted)</u>	<u>3635</u>	<u>3638</u>			
				<u>8-5/8"</u>	<u>284'</u>	<u>none</u>
				<u>5-1/2"</u>	<u>3638'</u>	<u>none</u>

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

200 sacks of 50/50 Poz. and 3% Calcium Chloride were pumped down the 8-5/8"
and 5-1/2" annulus at the same time. Shutin Pressure 300%.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____

STATE OF Oklahoma COUNTY OF Tulsa, ss.

M. R. Taylor, Mgr. of Production (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) M R Taylor
3232 First National Tower-Tulsa, OK 74103
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of September, 19 82

Mildred Carter
Mildred Carter Notary Public.

My Commission expires: 5/11/83

WELL LOG

15.185.10666.0000

Nadel and Guseman

FISCHER E No. 2

NW SW SW 25-21-13W
Stafford County, Kansas

Comm: 10-17-51

Comp: 10-30-51

Casing: 8-5/8" 284' w/225 sex
5-1/2" 3638' w/125 sex

Formation	Depth
Sand, shale and red bed	284
Red bed, sand and shells	525
Sand, red bed and shale	708
Anhydrite	750
Red bed, shale and shells	1430
Shale and shells	1575
Broken lime	1665
Lime and shale	1890
Shale and shells	1990
Shale, lime and shells	2120
Lime and shale	2515
Shale, lime and shells	2640
Lime and shale	2800
Broken lime	2900
Lime and shale	2970
Lime - hard	2999
Shale	3010
Lime	3045
Broken lime and shale	3145
Lime and shale	3225
Lime	3233
Shale and lime	3303
Lime	3535
Cherty lime	3563
Cherty Viola	3588
Shale and sand	3638

GEOLOGICAL TOPS

Heebner	3158
Brown Lime	3286
Lansing	3303
Base Lansing	3535
Viola	3535
Simpson	3588
Arbuckle	3634
Simpson Sand	3627
Green Shale	3631
R.T.D.	3638

STATE CORPORATION COMMISSION
 RECEIVED
 AUG 16 1982
 CONSERVATION DIVISION
 Wichita, Kansas

REC'D

STATE OF KANSAS

COUNTY OF SEDGWICK

ss:

L. C. Hay, of lawful age, deposes and states that the above depths and formations and true as taken from the daily drilling log of the Fischer E No. 2 in the NW SW SW 25-21-13W, Stafford County, Kansas.

Subscribed and sworn to before me this 2nd day of November, 1951.

L. C. Hay

Notary Public

My commission expires Nov. 3, 1952