

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15.185.10649.0000

API NUMBER N/A

LEASE NAME Fischer

WELL NUMBER A-3

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 25 TWP. 21 RGE. 13W ~~13W~~ (W)

COUNTY Stafford

Date Well Completed

Plugging Commenced 3-23-92

Plugging Completed 4-1-92

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Nadel & Gussman

ADDRESS 3200 National Twr Tulsa, Ok. 74103

PHONE#(918) 583-3333 OPERATORS LICENSE NO. 5337

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by Duane Rankin (KCC District Agent's Name).

Is ACO-1 filled?, If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3615'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	301'	none
				5 1/2"	3614'	2493'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Sanded bottom to 3550' ran 5 sacks cement. Shot pipe @2810', 2732', 2611', 2493'. Pumped 300 lbs. of hulls, 10 gel, 50 cement, 10 gel, 100 lbs. of hulls 100 sacks of cement 60/40 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Kelso Casing Pulling, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well filed that the same are true and correct, so help me God.


(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 2 day of April, 19 92

Irene Herzberg
Notary Public

My Commission Expires:



WELL LOG

Nadel and Gussman

Fischer A-3

NE SE SW 25-21S-13W
Stafford County, Kans.

Comm: 9-17-51
Comp: 10-1-51

Casing: 301' 8-5/8" W/200 sax
3614' 5-1/2" W/150 sax

Surface	71
Sand and red bed	312
Red bed and shale	690
Anhydrite	730
Red bed and shale	765
Shale and shells	1455
Broken lime	1550
Lime and shale	1635
Shale and Anhydrite	1790
Lime	1920
Shale and Lime	2145
Shale, lime and shells	2255
Shale and shells	2380
Lime	2462
Lime and shale	2620
Lime	2700
Broken lime	2800
Lime and shale	2870
Lime	2970
Broken lime and shale	3085
Lime	3192
Lime and shale	3255
Lime	3525
Cherty lime and shale	3565
Lime	3595
Shale	3600
Simpson shale and sand	3613
Arbuckle Dolomite	3615

GEOLOGICAL TOPS

Heebner	3136
Brown Lime	3262
Lansing-Kansas City	3280
Viola Residual Chert	3524
Simpson	3600
Arbuckle	3615

RECEIVED
STATE CORPORATION COMMISSION

FEB 20 1992
CONSERVATION DIVISION
WICHITA, KANSAS

STATE OF KANSAS }
COUNTY OF SEDGWICK } SS

L. C. Hay, of lawful age, deposes and states that the above formations and depths are true and correct as shown by the daily drilling log of the Fischer A-3 in the NE SE SW 25-21-13W, Stafford County, Kansas.

2 L. C. Hay

Subscribed and sworn to before me this 4th day of October, 1951.

Walter Burt
Notary Public

My commission expires Nov. 3, 1952