

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
240 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-185-10650-0001

LEASE NAME Fischer

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER B-1

990 Ft. from S Section Line

330 Ft. from E Section Line  
SW SW SE

SEC. 25 TWP. 21 RGE. 13W (E) or (W)

COUNTY Stafford

Date Well Completed \_\_\_\_\_

Plugging Commenced 6-3-93

Plugging Completed 6-15-93

LEASE OPERATOR Nadel and Gussman

ADDRESS 3200 First National Tower Tulsa, Okla. 74103

PHONE# (913) 583-3333 OPERATORS LICENSE NO. 5337

Character of Well Inject.

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on \_\_\_\_\_ (date)

by Duane Rankin (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, Is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3652'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	269'	none
				5-1/2"	3629'	299'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Plugged off bottom with sand to 3331' and 5 sacks cement. Well parted @299', pulled 299' of 5-1/2" casing. Plugged surface with 300# hulls and 300 sacks cement, 60/40 pos, 6% gel. Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Nadel and Gussman

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 23rd. day of June

RECEIVED  
STATE CORPORATION COMMISSION

Irene Herzberg  
Notary Public

JUN 24 1993

My Commission Expires: \_\_\_\_\_



CONSERVATION DIVISION  
Form C  
Rev. 10-83

RESERVE DRILLING COMPANY, INC.

703 UNION NATIONAL BANK BUILDING  
WICHITA, KANSAS

Nadel and Gussman

FISCHER "B" 1

SWc SE/4 25-23-13W  
Stafford County, Kansas

Date Spudded 10-6-48  
Date Completed 10-17-48

Casing: 269' 8 $\frac{1}{4}$ " 200 sax  
3629' 5 $\frac{1}{2}$ " 125 sax

<u>Formation</u>	<u>Depth</u>
Sand and shale	290
Sand, shale and shells	740
Shale and shells	1500
Broken lime	1700
Broken lime and shale	1850
Broken lime	2345
Shale and shells	2435
Shale and lime	2530
Shale and shells	2880
Shale and lime	2940
Lime	3020
Lime and shale	3135
Broken Lime	3185
Shale and broken lime	3255
Lime	3575
Shale	3628
Lime	3632

T.D.

RECEIVED  
STATE CORPORATION COMMISSION  
MAY - 1 1993  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above formations and depths are true and correct as taken from the daily drilling reports of the Fischer "B" 1 Well.

L. G. Hay  
President - Reserve Drilling Company

Subscribed and sworn to before me this 23rd day of October, 1948.

Paul Bass  
Notary Public

My commission expires Nov. 3, 1948