

STATE OF KANSAS
STATE CORPORATION COMMISSION
100 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15.185.10658.0001

LEASE NAME Fischer

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER B-9

2310 Ft. from S Section Line

1650 Ft. from E Section Line
NE NW SE

SEC. 25 TWP. 21 RGE. 13W (E) or (W)

COUNTY Stafford

Date Well Completed _____

Plugging Commenced 6-1-93

Plugging Completed 6-15-93

LEASE OPERATOR Nadel and Gussman

ADDRESS 3200 First National Tower Tulsa, Okla. 74103

PHONE# (918) 583-3333 OPERATORS LICENSE NO. 5337

Character of Well Inject.

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by Duane Rankin (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3694'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	327'	none
				5-1/2"	3620'	2305'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set. Plugged off bottom with sand to 3322' and 5 sacks cement. Shot pipe @2600', 2407', 2305'. Pulled 2305' of 5-1/2" casing. Plugged surface with 300# hulls, 10 gel, 50 cement, 10 gel, 200 # hulls and 125 cement, 60/40 pos, 6% gel. Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Nadel and Gussman

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 23rd. day of June

RECEIVED
STATE CORPORATION COMMISSION

Irene Herzberg
Notary Public

JUN 24 1993

My Commission Expires: _____



CONSERVATION DIVISION
Revised 05-88

NADEL AND GUSSMAN

FISCHER B-9 WELL

NE NW SE 25-21-13W
Stafford County, Kansas.

Comm: 10-1-52
Comp: 10-10-52

Casing: 8-5/8" 127' w/300 Sax
5-1/2" 3620' w/150 Sax

Formations	Depth
Sand and gravel	330
Red bed and shale	640
Shale	699
Anhydrite	725
Shale and shells	1570
Broken lime	1705
Lime and shale	3383
Lime	3528
Chert and shale	3577
Shale, Simpson and Arbuckle	3622
R.T.D.	3622

Geological Tops

Heebner Shale	3148
Brown Lime	3274
Lansing-K.C.	3292
Viola	3530
Simpson Sand	3594
Arbuckle	3619

RECEIVED
STATE CORPORATION COMMISSION

MAY - 1 1993

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
 { SS
COUNTY OF SEDGWICK)

L. C. Hay, of lawful age, deposes and states that the above formations and depths are correct as shown by the daily drilling log of the Fischer B-9 Well in the NE NW SE of 25-21S-13W, Stafford County, Kansas.

L. C. Hay

Subscribed and sworn to before me this 13th day of October, 1952

Nola Bobb
Notary Public

My commission expires Nov. 3, 1952