

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

STAFFORD County. Sec. 22 Twp. 21s Rge. 13W (#) X (W)

Location as "NE/CNW/SW" or footage from lines SE SE NW

Lease Owner PETROLEUM, INC.

Lease Name HOFFMAN Well No. 1

Office Address ROUTE 2, GREAT BEND, KANSAS

Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE

Date well completed JUNE 29, 1962

Application for plugging filed JUNE 29, 1962

Application for plugging approved JUNE 29, 1962

Plugging commenced JUNE 29, 1962

Plugging completed JUNE 30, 1962

Reason for abandonment of well or producing formation NO PRODUCIBLE FORMATIONS.

If a producing well is abandoned, date of last production NONE 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well W. L. LACKAMP

Producing formation --- Depth to top --- Bottom --- Total Depth of Well 3707 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	277'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

MUDDED UP WITH HEAVY MUD TO 180' FOLLOWED BY WOODEN PLUG. PLACED 20 SACKS CEMENT THROUGH DRILL PIPE ONTO PLUG. MUDDED UP WITH HEAVY MUD TO 35' FOLLOWED BY WOODEN PLUG AND 10 SACKS CEMENT TO BASE OF WELL CELLAR.

RECEIVED
STATE CORPORATION COMMISSION

JUL 16 1962

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor GARVEY DRILLING COMPANY
Address ROUTE 2, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.
DON SEARLE (employee of owner) or ~~known owner~~ of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. DON SEARLE, DIST. PROD. SUPT.

(Signature) Don Searle

ROUTE 2, GREAT BEND, KANSAS (Address)

SUBSCRIBED AND SWORN TO before me this 13TH day of JULY, 1962

My commission expires APRIL 13, 1963.

Arthur J. ... Notary Public.



WELL LOG

15.185.01368.0000

COMPANY **PETROLEUM, INCORPORATED**

SEC. 22 T. 21S R. 13W

FARM **HOFFMAN "I" NO. 1**


LOC. **SE, SE, NW**

TOTAL DEPTH **3707'**

COUNTY **STAFFORD CO., KANSAS**

COMM. **June 21, 1962** COMP. **June 30, 1962**

CONTRACTOR **GARVEY DRILLING COMPANY**



CASING **8-5/8" @ 277' w/225 sax.**

ELEVATION **1881' D.F.**

PRODUCTION **D & A**

FIGURES INDICATE BOTTOM OF FORMATIONS

85	Surface clay & sand
95	Hard sand
130	Blue clay
285	Shale
738	Shale & red bed
770	Anhydrite
1095	Shale
1500	Shale w/lime streaks
1820	Lime & shale
2055	Lime
2815	Shale & lime
3090	Lime & shale
3115	Shale
3219	Lime
3318	Shale
3640	Lime
3707	Chert
3707	T. D.

RECEIVED
 STATE CORPORATION COMMISSION
 JUL 16 1962
 CONSERVATION DIVISION
 Wichita, Kansas

State of KANSAS }
 County of BARTON } ss

I, VERNE A. MORRIS of GARVEY DRILLING COMPANY

upon oath state the above and foregoing is a true and correct copy of the log of the #1 HOFFMAN "I" well.

Subscribed and sworn to before me this 12th day of July 19 62

My Commission Expires: April 14, 1963

Archer J. Piles
 NOTARY PUBLIC