

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County, Sec. 22 Twp. 21S Rge. (E) 13 (W)

Location as "NE/CNW/SW" or footage from lines SW SE SW  
Lease Owner Circle Oil Company, Inc.  
Lease Name SIPES Well No. 1  
Office Address 500 Bitting Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed April 14, 1966  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced April 14, 1966  
Plugging completed April 14, 1966  
Reason for abandonment of well or producing formation

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie Elving  
Producing formation Depth to top Bottom Total Depth of Well 3721 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface Casing	0	286	8-5/8"	4/7/66	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy Mud from Total Depth to 275 Feet; Hull Plug and Wooden Plug and 25 sacks Cement through the Drill Pipe; Heavy Mud to 40 feet; 1/2 sack Hulls and Plug bridged and 10 sacks Cement to base of cellar; 2 sacks in Rat Hole. Job completed at 3:45 P.M.

RECEIVED  
APR 20 1966  
CONSERVATION DIVISION  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sage Drilling Co., Inc.  
Address 500 Bitting Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Lawrence F. Gray (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Lawrence F. Gray  
500 Bitting Building, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of April, 1966

My commission expires November 26, 1966  
Louise K. Whitted - Notary Public.

DRILLERS LOGSIPES NO. 1

CASING RECORD:	COMPANY:	Circle Oil Co.	DESCRIPTION:
8-5/8" @ 286'	CONTRACTOR:	Sage Drilling Co.	SW SE SW
w/275 sax cement	COMMENCED:	April 7, 1966	Sec. 22-21S-13W
TOTAL DEPTH:	COMPLETED:	April 14, 1966	Stafford Co., Kansas
3721'			ELEVATION: 1885 KB

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil & Sand	0	96	
Hard Sand & Pyrite	96	100	
Sand	100	129	
Shale & Sand	129	286	
Shale, Red Bed & Sand	286	725	
Anhydrite	725	750	
Red Bed & Shale	750	1220	
Shale & Shells	1220	1500	
Lime & Shale	1500	2278	
Shale & Lime	2278	2595	
Lime & Shale	2595	3721	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING COMPANY, INC.

By Lawrence F. Gray  
Lawrence F. Gray

Subscribed and sworn to before me this 18th day of April, 1966.

Louise K. Whitted  
Louise K. Whitted - Notary Public

My commission expires:  
November 26, 1966.