

WELL PLUGGING RECORD

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging of formations.

Stafford County. Sec. 222 Twp. 21 Rge. 13. (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines. NW NW NW

Lease Owner: PETROLEUM, INC.

Lease Name: Hoffman B Well No. 1

Office Address: 100 Derby Building, Wichita, 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole): Dry Hole

Date well completed: December 30, 1949


Application for plugging filed: March 11, 1950

Application for plugging approved: March 8, 1950

Plugging commenced: February 2, 1950

Plugging completed: March 3, 1950

Reason for abandonment of well or producing formation: Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production: 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well: C.D. Stough, Box 207 Great Bend, Kansas

Producing formation: Depth to top: Bottom: Total Depth of Well: 3671 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	321'	
				5 1/2"	3670'	2800'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged back to 3667' with Lane Well Plug.

Filled back to 3400'. Dumped 5 sacks of cement at 3400'. Shot pipe off at 2800'.

Pulled pipe and dumped mud to 320'. Set rock bridge at 320'. Put 15 sacks of cement at 320'. Mudded hole to 30'.

Finished mudding hole and put 6 sacks of cement at top of surface pipe.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to: PETROLEUM, INC. MAR 18 1950

Address: 100 Derby Building, Wichita 2, Kansas

3-13-50

STATE OF KANSAS, COUNTY OF SEDGWICK, KANSAS

Eric H. Jager (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) Eric H. Jager

100 Derby Bldg. Wichita 2, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 11th day of March, 1950

My commission expires October 27, 1952.

Margaret Bradshaw Notary Public.



COMPANY: Petroleum, Inc.
 CONTRACTOR: Jackson Drilling Corp.
 FARM: Hoffman B-1
 LOCATION: NW NW NW Section 22 21 13
 Stafford Co., Kansas
 ELEVATION: 1890
 COMMENCED: December 12, 1949
 COMPLETED: December 30, 1949

				<u>Tops</u>
0	to	60	Sand & Shale	
68	to	73	Pyrite	
73	to	98	Pyrite & sand	755 Anhydrite
98	to	330	pyritic shale	3196 Heebner
330	to	390	Shale & shells	3217 Toronto
390	to	755	Red bed	3232 B.O.
755	to	775	Anhydrite	3322 Br. Lime
775	to	1450	Shale & shells	3337 Lansing
1450	to	1570	Salt & shale	3553 B.K.C.
1570	to	1625	Shale & shells	3569 P.B.C.
1625	to	2955	Lime & shale	3576 Viola
2955	to	3015	Lime	3614 Simpson
3015	to	3355	Shale & lime	3665 Arbuckle
3355	to	3554	Lime	
3554	to	3563	Shale	
3563	to	3576	Lime	
3576	to	3615	Cherty Lime	
3615	to	3620	Shale	
3620	to	3665	Shale & lime	
3665	to	3670	Arbuckle	
		3670 T.D.		

8 5/8" casing set at 323 feet - Cemented with 125 sacks cement and 2 sacks calcium chloride

5 1/2" casing set at 3670 feet.

Measurements from top of derrick floor.

C E R T I F I C A T E

I, Clare A. Stewart, do hereby certify that the above and foregoing is a true and correct copy of log of the Hoffman B-1, Section 22-21-13, Stafford County, Kansas, as reflected by files of the Jackson Drilling Corporation.

Clare A. Stewart
 Clare A. Stewart

Subscribed and sworn to before me, a Notary Public, within and for Johnson County, Kansas, this 5th day of January 1950.

Dorothy J. Wilson
 Dorothy J. Wilson

My Commission expires November

