

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-185-20,583

LEASE NAME Sipes A

WELL NUMBER 3

         Ft. from S Section Line

         Ft. from E Section Line

SEC. 22 TWP. 21SRGE. 13(E)or(W)

COUNTY Stafford

Date Well Completed 11/22/71

Plugging Commenced 2/4/87

Plugging Completed 2/6/87

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR General Oil Company, Inc.

ADDRESS 1540 N. Braodway, Suite 203

PHONE#(316) 263-8588 OPERATORS LICENSE NO. 9069

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? yes

Which KCC Office did you notify? Dodge City - J.H. Metz

Is ACO-1 filed? yes If not, is well log attached? yes

Producing Formation Arbuckle Depth to Top 3678 Bottom 3687 T.D. 3695

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>see attached</u>		<u>surface</u>	<u>238'</u>	<u>8 5/8"</u>	<u>238'</u>	<u>none</u>
		<u>surface</u>	<u>3693</u>	<u>4 1/2"</u>	<u>3693'</u>	<u>288 (approximately)</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from          feet to          feet each set.  
see attached

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor General Oil Company, Inc. License No. 9069

Address 1540 N. Braodway, Suite 203

STATE OF Kansas COUNTY OF Sedgwick, ss.

John C. Bannister (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) [Signature]

(Address) 1540 N. Broadway, Suite 203

SUBSCRIBED AND SWORN TO before me this 26th day of February, 1987

Margaret R. Venema  
Notary Public FEB 27 1987

My Commission Expires: September 20, 1989





*Robert L. Moorehead* Consulting Petroleum Engineer

ENGINEERING • WELLSITE SUPERVISION • DRILLING/COMPLETION/PRODUCTION/EVALUATION

1410 WESTERN AVENUE • (316) 672-7737  
PRATT, KANSAS 67124

RECEIVED  
2-9-87

General Oil Company  
SIPES No. A-3  
P&A REPORT

February 6, 1987

- 2/4/87 MIRU Kirkman derrick. POH & LD 3 jts (121') 4½" casing. FL @ 15'. Ran 7 3/8" impression block on 2 7/8" tbg to 231' (No marks on inside-marks around outside edge indicating reduced size hole). Ran 6" impression block on 2 7/8" tbg to 288'. Impression indicates 4½ csg sliver looking up. PU & TIH w/open ended 2 3/8" tbg. Spudded & rotated thru tight spot @ 288'. Landed 2 3/8 tbg @ 3441' (all of 2 3/8" tbg on location). SION @ 4:30 PM.
- 2/5 Allied spotted 35 sxs 60/40 pozmix w/75# hulls @ 3441'. Pulled tbg to 2475' & spotted 10 sxs gel. Pulled tbg to 900' & spotted 100 sxs Class A cmt w/25# hulls. POH w/tbg and shut down 2½ hrs. Tagged cmt @ 580' w/wireline. TIH w/tbg to 546' & spotted 50 sxs 60/40 pozmix cmt w/100# hulls. Pulled tbg to 257'. Shut down 1½ hrs & tagged cmt @ 400' w/wireline. TIH to 386' & spotted 50 sxs 60/40 pozmix cmt w/100# hulls. POH w/tbg. Shut down 3/4 hr & tagged cmt @ 240' w/wireline. TIH w/tbg to 225' and circulated 80 sxs 60/40 pozmix cmt to surface. TOH w/tbg. Note: Had complete circulation during spotting of all cmt plugs and gel spacer. Released rig @ 4 PM.
- 2/6 Tagged cmt in 8 5/8" csg @ 5' below ground level.

SUMMARY OF CEMENT PLUGS

80 sxs 60/40 Pozmix cmt 5' below ground level to 225'  
50 sxs 60/40 Pozmix cmt 240' to 386'  
50 sxs 60/40 Pozmix cmt 400' to 546'  
100 sxs Common cmt 580' to 900'  
10 sxs gel spotted @ 2475'  
35 sxs 60/40 Pozmix cmt 2961'(calculated) to 3441'

The KCC representative, Mr. J. H. Metz, was on location during plugging operations and was completely satisfied.

Respectfully submitted,

*Robert Moorehead*  
Robert Moorehead

STATE CORPORATION COMMISSION

FEB 27 1987

CONSERVATION DIVISION  
Wichita, Kansas