

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15,185-20583

LEASE NAME Schulz

WELL NUMBER #3

SPOT LOCATION SW NW NE

SEC. 22 TWP. 21 RGE 13 (E) or (W)

COUNTY Stafford

Date Well Completed _____

Plugging Commenced 9-27-85

Plugging Completed 10-25-85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Woodman-Iannitti Oil Company

ADDRESS Box 308, Great Bend, Kansas 67530

PHONE # (316) 792-1934 OPERATORS LICENSE NO. 6588

Character of Well oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? One (1)

Is ACO-1 filed? _____ If not, is well log attached? With application

Producing formation _____ Depth to top _____ bottom _____ T.D. 3672'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	295'	None
				5-1/2"	3658'	2,457.85'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.
Dumped sand to 3600' and 5 sacks cement. Shot casing at 3000', 2700' and 2500'. Pulled 78 joints of 5-1/2" casing. Squeezed well with 2 sacks hulls, 10 sacks gel, 50 sacks cement, 10 sacks gel, 1 sack hulls, released plug and pumped 125 sacks 60/40 pozmix cement with 6% added gel and 3% calcium chloride. Maximum pressure was 800 psi and shutin 400 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111
Address Box 698, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.
(Signature) James W. Rockhold
(Address) Box 698, Gt. Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 4th day of November, 1985

STATE NOTARY PUBLIC
KANSAS
IONA M. LEATHERMAN
Barton County, Kansas
My Appt. Exp. 9-26-87

RECEIVED
Iona M. Leatherman
STATE CORPORATION COMMISSION Notary Public

My Commission expires: _____

NOV 5 1985

WOODMAN & IANNITTI DRILLING COMPANY

Rotary Drilling Contractors

15.185.20583.0000

1008 UNION NATIONAL BUILDING
WICHITA, KANSAS 67202

May 29, 1975

Company;	Woodman & Iannitti Drilling Co.
Farm;	#3 Schulz
Location;	SW NW NE
Section;	22-21-13W
County;	Stafford
Contractor;	Woodman & Iannitti Drilling Co.
Comm;	May 20, 1975
Compl;	May 28, 1975
Total Depth;	3672'
Casing;	8 5/8" @ 295 w/200 sx 5 1/2" @ 3658 w/100 sx

Figures Indicate Bottom Of Formations:

90	Sand
195	Shale & Sand Streaks
295	Shale & Sand
400	Shale
735	Red Bed & Shale
750	Anhy
985	Shale & Shells
1610	Shale & Shells
1700	Shale & Shells
2225	Lime
2790	Lime & Shale
3110	Lime
3180	Lime
3268	Lime & Shale
3355	Shale & Lime
3510	Lime
3515	Lime
3600	Lime & Chert
3610	Lime
3660	Lime
3672	Arbuckle

I certify the above to be a true and correct copy of the driller's log to the best of my knowledge and belief.

Woodman & Iannitti Drilling Co.

K. T. Woodman
K. T. Woodman

RECEIVED
STATE CORPORATION COMMISSION

SEP 3 1975

CONSERVATION DIVISION
Wichita, Kansas