

ATE OF KANSAS
ATE CORPORATION COMMISSION
D. S. Market, Room 2078
chita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15.185.01725.0000

API NUMBER Drilled 1943

LEASE NAME Krone

WELL NUMBER #1

660' Ft. from S Section Line

660 Ft. from W Section Line

SEC. 22 TWP. 21 RGE. 13 (E) or (W)

COUNTY Stafford

Date Well Completed _____

Plugging Commenced 8-28-98

Plugging Completed 9-1-98

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

EASE OPERATOR Globe Operating, Inc.

DRESS P.O. Box 12 Great Bend, Kansas 67530

PHONE#(316) 792-7607 OPERATORS LICENSE NO. 6170

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3677'

How depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	380'	None
				5-1/2"	3669'	1812'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugging material was used, state the character of same and depth placed, from _____ feet to _____ feet each section. Plugged off bottom with sand to 3320' and 5 sks. cement. Shot pipe @2417', 2107', 1812', pulled up to 750', pumped 10 sks. gel and 50 sks. cement, pulled to 400', pumped 50 sks. cement, pulled to 10' and topped off with 10 sks. cement. 60/40 pos. 6% gel.

Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Globe Operating, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 11th day of September, 1998

[Signature]
Notary Public

My Commission Expires: _____

